



1700 S. Country Estates Rd.
 Liberal, Kansas 67905
 Phone 620-624-2277

FIELD SERVICE TICKET
 1717 05454 A

DATE 6/22 TICKET NO. _____

DATE OF JOB <u>6-22-15</u>	DISTRICT	NEW WELL <input type="checkbox"/>	OLD WELL <input checked="" type="checkbox"/>	PROD <input type="checkbox"/>	INJ <input type="checkbox"/>	WDW <input type="checkbox"/>	CUSTOMER ORDER NO.:
CUSTOMER <u>Merit Energy</u>	LEASE <u>Prairie View</u>		WELL NO <u>1-22</u>				
ADDRESS	COUNTY <u>Finney</u>	STATE <u>Ks.</u>					
CITY	STATE	SERVICE CREW <u>Daniel, Rogelio, Margarito</u>					
AUTHORIZED BY <u>Chad Hinz</u>	JOB TYPE: <u>242 Production</u>						
EQUIPMENT#	HRS	EQUIPMENT#	HRS	EQUIPMENT#	HRS	TRUCK CALLED	DATE <u>6-22-15</u> TIME <u>3:00</u>
<u>78938</u>	<u>1</u>					ARRIVED AT JOB	<u>6-22-15</u> <u>8:30</u>
<u>38117/19919</u>	<u>1</u>					START OPERATION	<u>10:00</u>
<u>30464/37724</u>	<u>1</u>					FINISH OPERATION	<u>11:00</u>
						RELEASED	<u>6-22-15</u> <u>12:00</u>
						MILES FROM STATION TO WELL	<u>50</u>

CONTRACT CONDITIONS: (This contract must be signed before the job is commenced or merchandise is delivered).

The undersigned is authorized to execute this contract as an agent of the customer. As such, the undersigned agrees and acknowledges that this contract for services, materials, products, and/or supplies includes all of and only those terms and conditions appearing on the front and back of this document. No additional or substitute terms and/or conditions shall become a part of this contract without the written consent of an officer of Basic Energy Services LP.

SIGNED: X
 (WELL OWNER, OPERATOR, CONTRACTOR OR AGENT)

ITEM/PRICE REF. NO.	MATERIAL, EQUIPMENT AND SERVICES USED	UNIT	QUANTITY	UNIT PRICE	\$ AMOUNT
CL 104	50/50 Poz	sk	255		2809 00
CC 111	Salt	lb.	1571		785 50
CC 201	Gilsonite	lb.	1280		857 60
CC 113	Gypsum	lb	1075		806 25
CC 103	6-15	lb	129		1612 50
CC 105	C-41P	lb	54		216 00
E 101	Heavy Equipment Mileage	mi	100		750 00
CE 240	Blending & Mixing Service Charge	sk	255		357 00
E 113	Proppant & Bulk Delivery Charges	tm	538		1343 75
CE 206	Depth Charge, 5001-6000'	4hrs	1		2880 00
CE 504	Plug Container Utilization Charge	job	1		250 00
E 100	Unit Mileage Charge - Pickups, Small V.	mi	50		225 00
S 003	Service Supervisor, first 8hrs. on loc.	ea	1		175 00
T 105	Cement Data Acquisition Monitor	ea	1		550 00

Well Prairie View 1-22

AFE 45063

GL 83061075

Office Hotcomb 145

Date 6/22/15

SUB TOTAL 84,900 90

[Signature]

SERVICE & EQUIPMENT	%TAX ON \$
MATERIALS	%TAX ON \$

TOTAL

SERVICE REPRESENTATIVE Daniel Beck

THE ABOVE MATERIAL AND SERVICE ORDERED BY CUSTOMER AND RECEIVED BY:

[Signature]

(WELL OWNER OPERATOR CONTRACTOR OR AGENT)

FIELD SERVICE ORDER NO.



Cement Report

Customer <i>Merit Energy</i>		Lease No.		Date <i>6-22-15</i>	
Lease <i>Prairie View</i>		Well # <i>1-22</i>		Service Receipt <i>1717 05454</i>	
Casing <i>5 1/2" 17lb.</i>		Depth <i>5195.87ft.</i>		County <i>Finney</i>	
State <i>Ks.</i>		Job Type <i>242 Production</i>		Formation	
Legal Description <i>22 24 33</i>		Pipe Data		Perforating Data	
Cement Data		Casing size <i>5 1/2" 17#</i>		Tubing Size	
Lead <i>50/50 Poz</i>		Depth <i>5195.87ft</i>		Shots/Ft	
<i>2.55sk</i>		Volume <i>119.5 bbl</i>		From	
<i>1.58^{ft}3/sk</i>		Max Press <i>2500psi</i>		To	
<i>7.36^{ft}4/sk</i>		Well Connection <i>P.C.</i>		From	
Tail in		Annulus Vol.		To	
Plug Depth <i>5151.25ft</i>		Packer Depth		From	
				To	
Time	Casing Pressure	Tubing Pressure	Bbls. Pumped	Rate	Service Log
<i>3:00</i>					<i>Call Out</i>
<i>7:15</i>					<i>Left Yard</i>
<i>8:30</i>					<i>On Location</i>
<i>8:45</i>					<i>Safety Meeting w/ BES Personnel</i>
<i>9:00</i>					<i>Rig Up</i>
<i>9:30</i>					<i>Safety Meeting w/ Rig Crew</i>
<i>9:55</i>					<i>Pressure Test to 2500psi</i>
<i>10:00</i>	<i>100</i>		<i>71.75</i>	<i>5.0</i>	<i>Pump 50/50 Poz</i>
<i>10:05</i>					<i>Shutdown by rig (no problems)</i>
<i>10:20</i>					<i>Shutdown/Wash Pump/ Drop Plug</i>
	<i>20</i>		<i>10</i>	<i>5.0</i>	<i>Displacement</i>
	<i>20</i>		<i>20</i>	<i>5.0</i>	
	<i>20</i>		<i>30</i>	<i>5.0</i>	
	<i>20</i>		<i>40</i>	<i>5.0</i>	
	<i>20</i>		<i>50</i>	<i>5.0</i>	
	<i>20</i>		<i>60</i>	<i>5.0</i>	
	<i>180</i>		<i>70</i>	<i>5.0</i>	
	<i>450</i>		<i>80</i>	<i>4.7</i>	
	<i>650</i>		<i>90</i>	<i>4.2</i>	
	<i>800</i>		<i>100</i>	<i>3.8</i>	
	<i>950</i>		<i>110</i>	<i>2.0</i>	<i>Slow Rate</i>
<i>10:55</i>	<i>1600</i>		<i>119.5</i>	<i>0</i>	<i>Land Plug Pressure up + wait</i>
<i>11:00</i>					<i>Release Back Float Held Job Complete</i>
Service Units	<i>78938</i>	<i>38117/19919</i>	<i>30464/37724</i>		
Driver Names	<i>Daniel</i>	<i>Rogelio</i>	<i>Margarito</i>		

James Carter
Customer Representative

Tyce Davis
Station Manager

Daniel Beck
Cementer