



CONSOLIDATED
Oil Well Services, LLC

4551
4451

TICKET NUMBER 49856
LOCATION Oklahoma KS
FOREMAN Fred Maden

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice #806112

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-20-15	4015	Ray Beals I-8	SE 1	18	21	MI
CUSTOMER JTC Oil Inc			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS 35790 Plum Creek Rd			712 Fre Mad			
CITY STATE ZIP CODE Osawatomie KS 66064			495 Har Bec			
			675 Mai Det			
			503 Tro Har			

JOB TYPE Longstring HOLE SIZE 5 7/8 HOLE DEPTH 700 CASING SIZE & WEIGHT 2 7/8 EUE
 CASING DEPTH 1691 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 2 1/2" Plug
 DISPLACEMENT 4.02 BBL DISPLACEMENT PSI _____ MIX PSI _____ RATE 40 RPM

REMARKS: Hold Safe to mixing. Establish pump rate - Mix + Pump 100# Gal flush. Mix + Pump 79 sks Thix blend IA Cement / 1/4" Cello flake/sk. Cement to surface. Flush pump + lines clean. Displace 2 1/2" Rubber plug to casing TP. Pressure to 800# PSI. Monitor pressure for 30 minutes MIT. Release pressure to set float valves. Shut in Casing.

Fred Maden

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE 0450	1	PUMP CHARGE	495	1500 ⁰⁰
CE 0002	25 mi	MILEAGE	495	17625
CE 0710	1/2 Minimum	Ton Miles Delivery	503	330 ⁰⁰
CE 0853	1 hr	80 BBL Vac Truck	675	100 ⁰⁰
		Sub Total		210825
		less 46%		- 970 ⁰³
				113822
CC 5860	79 sks	Thix blend IA Cement		1975 ⁰⁰
CC 5965	100#	Bentonite Gel		30 ⁰⁰
CC 6075	20#	Cello flake		40 ⁰⁰
CP 8176	1	2 1/2" Rubber Plug		45 ⁰⁰
		Sub Total		2090 ⁰⁰
		less 46%		- 961 ⁴⁰
				112860
			6%	SALES TAX 90 ²⁹
				ESTIMATED TOTAL 2357 ⁶²

Revin 3737

AUTHORIZATION Manuel Escobar TITLE _____ DATE (4365.95)

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.