



**CONSOLIDATED**  
Oil Well Services, LLC

TICKET NUMBER 49861  
LOCATION Ottawa KS  
FOREMAN Fred Mad

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-21-15	3372	Vesucky # 2-6i	NE 22	14	20	OG
CUSTOMER Grand Mesa			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 1700 N Water Front Hwy. Rt 600			712	Fred Mad		
CITY STATE ZIP CODE Wichita KS 67206			495	Harbor		
			675	Kel Dor		
			510	Tra Hor		

JOB TYPE Long string HOLE SIZE 5 7/8 HOLE DEPTH 762 CASING SIZE & WEIGHT 2 7/8 EUE  
CASING DEPTH 7520 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 2 1/2" Plug  
DISPLACEMENT 4.37 DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 46PM

REMARKS: Hold Safety meeting. Establish circulation. Mix & Pump 100# Gel Flush. Mix & Pump 100 sks Poz Blend I A Cement 2% Gel 5% salt 5# Kal Seal/sk. Cement to Surface. Flush pump & line clean. Displace 2 1/2" Rubber plug to casing TP. Pressure to 800# PSI. Monitor pressure for 30 minute MIT. Release pressure to set float valve. Shut in casing.

Mc Gown Drilling Fred Mad

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	495	
CE0002	25 mi	MILEAGE	495	
CE0710	1/2 minimum	Ton Miles Delivery	510	
WE0853	1 hr	80 BBL Vac Truck	675	
		Sub Total		
CB584D	100 SKS	Poz Blend I A Cement		
CC5965	265#	Bentonite Gel		
CC5326	193#	Granulated Salt		
CC6077	500#	Kal Seal		
CP8176	1	2 1/2" Rubber Plug		
		Sub Total		
			7.5%	
			SALES TAX	
			ESTIMATED	
			TOTAL	

RAVIN 3737  
AUTHORIZATION [Signature] TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.