

Log Book

Well No. I-1

Farm Greiken

KS Miami
(State) (County)


29 18 24
(Section) (Township) (Range)

For Triple T Oil
(Well Owner)

Town Oilfield Services, Inc.

1207 N. 1st East
Louisburg, KS 66053
913-710-5400

Thickness of Strata	Formation	Total Depth	Remarks
0-7	soil-clay	7	
33	Lime	40	
10	Shale	50	
18	Lime	68	
5	Shale	73	
2	Lime	75	
4	Shale	79	
6	Lime	85	Heath
24	Shale	109	
20	Sand	129	odor - no show
16	sandy shale	145	
146	Shale	291	
6	Lime	297	
9	Shale	306	
2	Lime	308	
8	Shale	316	
7	Lime	323	
16	Shale	339	
4	Lime	343	
5	Shale	348	
7	Sand	355	no Oil
29	Lime	384	
67	Shale	451	
4	sandy shale	455	
5	sand	460	mostly solid - good saturation
16	sandy shale	476	
2	sand	478	solid - good saturation



4684
4594

TICKET NUMBER 49873
LOCATION Ottawa KS
FOREMAN Fred Mader

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-30-15	7966	Gey Run # 2-1	NE 29	18	24	MI
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Triple J Oil			712	Fred Mader		
MAILING ADDRESS			495	Har Bee		
P.O. Box 339			675	Ki Rat		
CITY	STATE	ZIP CODE	578	Tro Har		
Louisburg	KS	66053				

JOB TYPE long string HOLE SIZE 5 7/8 HOLE DEPTH 560 CASING SIZE & WEIGHT 2 7/8 EUE
 CASING DEPTH 548 DRILL PIPE Def Fle TUBING @ 52 DS OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 25' x Plug
 DISPLACEMENT 3 BBL DISPLACEMENT PSI _____ MIX PSI _____ RATE 48 BPM

REMARKS: Hold Safety meeting - Establish Circulation Mix + Pump 100# Gel
Flush Mix + Pump 24 SKS Poz Blend I.A. Cement 2 1/2" 60
Cement to surface. Flush pump + lines clean. Displace 2 1/2"
Rubber plug to Baffle in casing. Pressure to 800# PSI.
Monitor pressure for 30 minutes MIT. Release pressure to
Set float valve. Shut in casing.

TDS Drilling - (was)

Fred Mader

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0430	1	PUMP CHARGE	495	1600.00
CE0007	30 mi	MILEAGE	495	214.50
CE0711	43 Minimum	Ten Miles Delivery	548	220.00
WE0853	1hr	80 BBL Vac Truck	675	100.00
		Sub Total		2034.50
		less 4670		-735.87
				1298.63
6870 CE05840	74 SKS	Poz Blend I.A. Cement		999.00
CE05965	224#	Bentonite Gel		67.80
CP8174	1	2 1/2" Rubber Plug		45.00
		Sub Total		1111.80
		less 4670		-511.15
				600.65
			870	SALES TAX
				ESTIMATED
				TOTAL
				1746.68

Revis 3737 AUTHORIZATION [Signature] TITLE _____ DATE 10-30-15

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form