

Miami County, KS
 Well: Gerken I-2
 Lease Owner: Triple T

Town Oilfield Service, Inc.
 (913) 837-8400

Commenced Spudding:
 10/20/2015

WELL LOG

Thickness of Strata	Formation	Total Depth
0-10	Soil-Clay	10
34	Lime	44
7	Shale	51
19	Lime	70
5	Shale	75
2	Lime	77
4	Shale	81
6	Lime	87
22	Shale	109
10	Sand	119
41	Sandy Shale	160
101	Shale	261
5	Lime	266
27	Shale	293
6	Lime	299
10	Shale	309
2	Lime	311
9	Shale	320
10	Lime	330
12	Shale	342
4	Lime	346
6	Shale	352
6	Sand	358
28	Lime	386
5	Shale	391
3	Lime	394
11	Shale	405
3	Lime	408
47	Shale	455
4	Sandy Shale	459
6	Sand	465
16	Sandy Shale	481
9	Sand	490
1	Shale	491
3	Lime	494
86	Shale	580-TD

Log Book

Well No. I-2

Farm Gecken

KS
(State)

Miami
(County)

29
(Section)

18
(Township)

24
(Range)

For Triple T oil
(Well Owner)

Town Oilfield Services, Inc.

1207 N. 1st East
Louisburg, KS 66053
913-710-5400

Gerken Farm: Miami County

KS State; Well No. I-2

Elevation 923

Commenced Spuding 10-20 20 15

Finished Drilling 10-23 20 15

Driller's Name Wesley Dollard

Driller's Name

Driller's Name

Tool Dresser's Name Ryan Ward

Tool Dresser's Name

Tool Dresser's Name

Contractor's Name TOS

29 18 24

(Section) (Township) (Range)

Distance from S line, 4425 ft.

Distance from E line, 2080 ft.

3 sacks 2 7/8 casing

8 hrs

5 7/8 borehole

CASING AND TUBING RECORD

10" Set _____ 10" Pulled _____

8" Set _____ 8" Pulled _____

7" Set 20 6 1/2" Pulled _____

4" Set _____ 4" Pulled _____

2" Set _____ 2" Pulled _____

CASING AND TUBING MEASUREMENTS

Feet	In.	Feet	In.	Feet	In.
521.35		Baffle			
554.00		Floor			
580 TD				2 7/8	

Thickness of Strata	Formation	Total Depth	Remarks
0-10	soil-clay	10	
34	Lime	44	
7	Shale	51	
19	Lime	70	
5	Shale	75	
2	Lime	77	
4	Shale	81	
6	Lime	87	Hertha
22	Shale	109	
10	sand	119	
41	sandy shale	160	odoc - slight show
101	Shale	261	
5	Lime	266	
27	Shale	293	
6	Lime	299	
10	Shale	309	
2	Lime	311	
9	Shale	320	
10	Lime	330	
12	Shale	342	
4	Lime	346	
6	Shale	352	
6	sand	358	no Oil
28	Lime	386	
5	Shale	391	
3	Lime	394	
11	Shale	405	



CONSOLIDATED
Oil Well Services, LLC

4/18/88
4528

TICKET NUMBER 49867
LOCATION Ottawa KS
FOREMAN Fred Madler

PO Box 884, Chanute, KS 66720
820-431-9210 or 800-467-8878

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-23-15	7969	Gorkan # T-2	NE 27	18	24	MI
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Triple T Oil			712	Fred Mad		
MAILING ADDRESS			495	Har Bee		
P.O. Box 339			675	Kid Det		
CITY	STATE	ZIP CODE	548	Tran Har		
Louisburg	KS	66053				

JOB TYPE Long string HOLE SIZE 5 7/8 HOLE DEPTH 580' CASING SIZE & WEIGHT 2 7/8 EOE
 CASING DEPTH 554' DRILL PIPE Baffle in TUBING 2 S21 OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 33' + Plug
 DISPLACEMENT 3.3288 DISPLACEMENT PSI _____ MIX PSI _____ RATE 43 BPM

REMARKS: Hold safety meeting. Establish pump rate. Mix Pump 100' Gal
Flush. Mix + Pump 70 sks Por Blend I.A. Cement 28 Gal. Cement
to surface. Flush pump lines clean. Displace 2 1/2" Rubber Plug to
Baffle in casing. Pressure to 800' ASI. Monitor Pressure for
30 minutes MIT. Release pressure to set float valve. Shift in
casing.

Tow Drilling (weekly)

Fred Madler

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	495	1500 ⁰⁰
LE0002	-	MILEAGE		N/C
CE0710	1/2 M/M/M/M	Tow Miles Delivery	548	220 ⁰⁰
WE0853	1 hr	80 Bbl Vac Truck	675	100 ⁰⁰
		Sub Total		1820 ⁰⁰
		Less 46%		-837 ²⁰
				982 ⁸⁰
CE5240	70 SKS	Por Blend I.A. Cement	945 ⁰⁰	
CE5965	218'	Bentonite Gel	165 ⁰⁰	
CP8176	1	2 1/2" Rubber Plug	45 ⁰⁰	
		Sub Total		1055 ⁰⁰
		Less 46%		-485 ⁴²
				569 ⁵⁸
			6%	SALES TAX
				45 ³³
				ESTIMATED TOTAL
				1598 ³¹
				(2968 ³³)

Form 8737

AUTHORIZATION _____ TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.