



# Log Book

Well No. T-8

Farm Gerken

KS Miami  
(State) (County)

29 18 24  
(Section) (Township) (Range)

For Triple T Oil  
(Well Owner)

**Town Oilfield  
Services, Inc.**  
1207 N. 1st East  
Louisburg, KS 66053  
913-710-5400



Thickness of Strata	Formation	Total Depth	Remarks
0-13	soil - clay	13	
33	Lime	46	
8	Shale	54	
22	Lime	76	
4	Shale	80	
2	Lime	82	
5	Shale	87	
6	Lime	93	Hertha
23	Shale	116	
5	sandy shale	121	
10	sand	131	odor - no show
2	limy sand	133	
27	sandy shale	160	
98	Shale	258	
6	limy sand	264	no Oil
38	Shale	302	
6	Lime	308	
16	Shale	324	
8	Lime	332	
15	Shale	347	
4	Lime	351	
6	Shale	357	
7	sand	364	no Oil
28	Lime	392	
66	Shale	458	
4	sandy shale	462	no Oil
2	sand	464	broken Oil - perf





**CONSOLIDATED**  
Oil Well Services, LLC

4/6 8/4  
4595

TICKET NUMBER 49890  
LOCATION Ottawa KS  
FOREMAN Fred Madar

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-30-15	7966	Gerken #T-8	NE 29	1E	24	MI
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Triple T Oil			712	Fred Mad		
MAILING ADDRESS			495	Har Bee		
Box 339			675	Kei Day		
CITY	STATE	ZIP CODE	548	Tre Nor		
Louisburg	KS	66053				

JOB TYPE Logging HOLE SIZE 5 7/8 HOLE DEPTH 560 CASING SIZE & WEIGHT 2 7/8  
CASING DEPTH 547 DRILL PIPE \_\_\_\_\_ TUBING 5 7/8 OTHER \_\_\_\_\_  
SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT In CASING \_\_\_\_\_  
DISPLACEMENT 388L DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 48 BPM

REMARKS: Hold Safety meeting. Establish Circulation. Mix & Pump  
100# Gal Flush. Mix & Pump 74 SKS Por Blend IA  
Cement 224 gal. Cement to surface. Flush pump & lines clean.  
Displace 2 1/2" Rubber plug to baffle in casing. Pressure to 800# PSI.  
Monitor Pressure for 30 minute MIT. Release pressure to set  
Flood Valve. Shut in Casing.

TOS Drilling

Fred Madar

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	495	1500.00
CE0002	-	MILEAGE		N/C
CE0711	1/2 minimum	Ten Miles Delivery	548	220.00
WE0853	1hr	\$0.80/hr Vac Truck	675	100.00
		Sub Total		1820.00
		less 46%		- 837.20
				982.80
CC5840	74 SKS	Por Blend IA Cement	999.00	
CC5965	224#	Bentonite Gel	67.20	
CP6176	1	2 1/2" Rubber Plug	45.00	
		Sub Total		1111.20
		less 46%		- 511.15
				600.05
			670	SALES TAX
				44.00
				ESTIMATED TOTAL
				1620.05

0821

Rev'n 3737

AUTHORIZATION [Signature] TITLE \_\_\_\_\_ DATE 3020-10

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form