



CONSOLIDATED
Oil Well Services, LLC

TICKET NUMBER 49850

LOCATION Off Lawa KS

FOREMAN Fred Mader

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-8-15	3372	Schmidt # 14-12	SE 15	14	30	06
CUSTOMER <u>Grand Mesa</u>			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS <u>1700 N water front Pkwy</u>			<u>712</u>	<u>Fve Mad</u>		
CITY <u>Wichita</u>	STATE <u>KS</u>	ZIP CODE <u>67206</u>	<u>495</u>	<u>Har Bec</u>		
			<u>675</u>	<u>Ki Dost</u>		
			<u>804</u>	<u>Tro Har</u>		

JOB TYPE long string HOLE SIZE 5 7/8 HOLE DEPTH 802 CASING SIZE & WEIGHT 2 7/8 EUS
 CASING DEPTH 783.70 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING 2 1/2" Plug
 DISPLACEMENT 4.56 BBL DISPLACEMENT PSI _____ MIX PSI _____ RATE 43 PM

REMARKS: Hold safety meeting, Establish circulation. Mix & Pump 100# Gel flush. Mix & Pump 110 SKS for Blend I-A Cement 2% Gel 5% Salt 5# Kol Seal/sk. Cement to surface. Flush pumps & lines clean. Displace 2 1/2" Rubber plug to casing TD. Pressure to 800# PSI. Monitor pressure for 30 min MIT. Release pressure to set & lock valve. Shut in casing

Mc Gown Drilling Fred Mader

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE		
CE0002		MILEAGE		
CE0710	<u>2/3 minimum</u>	<u>Ton Miles Delivery</u>		
WE0855	<u>1 hr</u>	<u>80 BBL Vac Truck</u>		
		<u>Sub Total</u>		
CC5840	<u>111 SKS</u>	<u>Poz Blend I-A Cement</u>		
CC5965	<u>287#</u>	<u>Bentonite Gel</u>		
CC5326	<u>214#</u>	<u>Granulated salt</u>		
CC6077	<u>555#</u>	<u>Kol Seal</u>		
CP8176	<u>1</u>	<u>2 1/2" Rubber Plug</u>		
		<u>Sub Total</u>		
			<u>7.53</u>	
			SALES TAX	
			ESTIMATED	
			TOTAL	

Revin 3737

AUTHORIZATION [Signature] TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the account records, at our office, and conditions of service on the back of this form are in effect for services I do