

JOB LOG

SWIFT Services, Inc.

DATE: 9-5-15 PAGE NO. 7

CUSTOMER: Downing & Nelson WELL NO: 1-21 LEASE: Hogan Family Trust JOB TYPE: Long String TICKET NO: 27042

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL)(GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1900							On Loc. Rig Laying Down D.P.
	2015							Start in hole 5 1/2" 14 # Csg. Insert Float Shoe 4454' Latch down Baffle 4427' Cen. # 1, #3, #5, #7, #9 Back to top #1
	2145							Drop Ball
	2210							Circulate + Rotate
	2230							Plug R.H. + M.H. 30-20sib
	2245		12					Pump 500gal Mud Flush
			20					2000 KCL Flush
	2250							Mix 125sib EA-2 Cement
			30					Finish mixing
								wash out pump + line
	2300							Displ. Latch down Plug
	2315		108					Plug down
								Release Press. Float hold
	2345							wash + Rack up tool Job Complete

*[Signature]*  
Rogers, Steve E., Isaac