

# ALLIED OIL & GAS SERVICES, LLC

Federal Tax I.D. #20-5975804

**WELL FILE**

067501

REMIT TO P.O. BOX 93999  
SOUTHLAKE, TEXAS 76092

SERVICE POINT: Oddy, KS

DATE <u>11-8-15</u>	SEC. <u>17</u>	TWP. <u>2</u>	RANGE <u>37</u>	CALLED OUT	ON LOCATION <u>2:00 a.m.</u>	JOB START <u>6:30 a.m.</u>	JOB FINISH <u>11:50 a.m.</u>
LEASE <u>Ardene</u>	WELL # <u>1-17</u>	LOCATION <u>McDonald N to Rd W, 1/2 W, 1/2 W</u>			COUNTY <u>Cherokee</u>	STATE <u>KS</u>	
OLD OR <u>NEW</u> (Circle one)				<u>Into</u>			

CONTRACTOR Beredex 10  
 TYPE OF JOB Production (Long String)  
 HOLE SIZE 7 7/8 T.D. 4805'  
 CASING SIZE 5 1/2 (155') DEPTH 4810'  
 TUBING SIZE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 DRILL PIPE \_\_\_\_\_ DEPTH \_\_\_\_\_  
 TOOL \_\_\_\_\_ DEPTH \_\_\_\_\_  
 PRES. MAX \_\_\_\_\_ MINIMUM \_\_\_\_\_  
 MEAS. LINE \_\_\_\_\_ SHOE JOINT 42'  
 CEMENT LEFT IN CSG. 42'  
 PERFS. \_\_\_\_\_  
 DISPLACEMENT 115.48 bbl H<sub>2</sub>O

OWNER Same  
 CEMENT  
 AMOUNT ORDERED 450 sks 60/40 8' gel  
3/4" Flo-seal 350 sks Com. 10' salt  
5" gilsonite, 2' gel

EQUIPMENT  
 PUMP TRUCK CEMENTER Paul Bernier  
 # 431 HELPER Darren Racette  
 BULK TRUCK  
 # 891/287 DRIVER Monty Phillips  
 BULK TRUCK  
 # 898/310 DRIVER Ivan Carrillo (Liberal)

COMMON	<u>350 sks @ 17.90</u>	<u>6265.00</u>
POZMIX	@	
GEL	@	
CHLORIDE	@	
ASC	@	
gilsonite	<u>1750 # @ .98</u>	<u>1751.00</u>
salt	<u>1830 # @ .68</u>	<u>1237.60</u>
Lite 60/40/8	<u>450 sks @ 19.89</u>	<u>8950.50</u>
Flo-seal	<u>338 # @ 2.97</u>	<u>1003.86</u>
	@	
	@	
	@	
	@	

TOTAL 19,207.96  
 DISCOUNT 48% 9219.82

REMARKS:

Run Pipe / Float equip, Break Circ / Drop ball, pumped through shoe @ 900', Circ + Reciprocate, mix 20 sks in m.d., mix 30 sks in R.H., mix 400 sks Lite, tail w/ 350 sks Com, work up to pit, release plug, Displace w/ water. Plug did land @ 4805', Lift 200', Float did hold, cement did circulate.  
Thank You!  
Paul + Crew

SERVICE

HANDLING	<u>945.70 ft<sup>2</sup> @ 2.48</u>	<u>2345.34</u>
MILEAGE	<u>39.63 hrs @ 2.75</u>	<u>5447.13</u>
DEPTH OF JOB	<u>4810'</u>	
PUMP TRUCK CHARGE		<u>2765.75</u>
EXTRA FOOTAGE	@	
HV MILEAGE	<u>50 @ 7.70</u>	<u>385.00</u>
LV MILEAGE	@	<u>N/C</u>
	<u>Head manifold @</u>	<u>N/C</u>
	@	

TOTAL 10,945.22  
 DISCOUNT 48% 5253.70

CHARGE TO: Beredex Inc.  
 STREET \_\_\_\_\_  
 CITY \_\_\_\_\_ STATE \_\_\_\_\_ ZIP \_\_\_\_\_

PLUG & FLOAT EQUIPMENT

Weatherford	<u>5 1/2</u>	
AFU Float shoe	@	<u>545.00</u>
Latchdown plug Assy	@	<u>660.00</u>
Centralizers	<u>20 @ 57.00</u>	<u>1140.00</u>
Retip. Scrubbers	<u>24 @ 89.00</u>	<u>2136.00</u>
	@	

TOTAL 4481.00  
 DISCOUNT 48% 2150.88

SALES TAX (if Any) \_\_\_\_\_  
 TOTAL CHARGES 39,634.18  
 DISCOUNT 16,624.40 (48%) IF PAID IN 30 DAYS  
 NET TOTAL 18,009.77 IF PAID IN 30 DAYS

To: Allied Oil & Gas Services, LLC.  
 You are hereby requested to rent cementing equipment and furnish cementer and helper(s) to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read and understand the "GENERAL TERMS AND CONDITIONS" listed on the reverse side.

PRINTED NAME \_\_\_\_\_  
 SIGNATURE Ed Dawes