

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report

Ticket No. 2789
 Foreman Kevin McCoy
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
5-19-16	1180	Fulson B #9				C9	KS	
Customer SM oil & GAS INC.			Safety Meeting KM DG RL		Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 189					102	RICK L.		
City SKIATOOK			State OK		113	DAVE G.		
Zip Code 74070								

Job Type TOP CASE Hole Depth 2109' Slurry Vol. 26.5 BBL Tubing _____
 Casing Depth 2105' Hole Size 7 7/8" & 12 1/4" Slurry Wt. 13.9 # Drill Pipe _____
 Casing Size & Wt. 5 1/2 17" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: SAFETY MEETING: RAN 1" HYDRILL DOWN ANNULUS OF 5 1/2" CASING IN 12 1/4" HOLES. WASH DOWN TO FIRM CEMENT TOP @ 333'. CIRCULATE W/ 40 BBL FRESH WATER TO CLEAN UP HOLE. MIXED 105 SKS 50/50 FOZMIX CEMENT W/ 4% GEL @ 13.9 #/gal yield 1.41 = 26.5 BBL SLURRY. GOOD CEMENT TO SURFACE. SHUT DOWN. PULL 1" TUBING. JOB COMPLETE. RIG DOWN.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 101	1	Pump Charge	840.00	840.00
C 107	30	Mileage	3.95	118.50
C 204	105 SKS	50/50 FOZMIX CEMENT	11.25	1181.25
C 206	350 #	GEL 4%	.20 #	70.00
C 108A	4.41 TONS	Ton Mileage	M/C	345.00
C 118	330'	1" RENTAL ELEVATOR, WASH HEAD	M/C	200.00
			Sub Total	2754.75
			Less 5%	
			Sales Tax 8.5%	123.36

Thank You

Authorization Witnessed By Joel Title _____ Total 2734.20

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.