



CONSOLIDATED
Oil Well Services, LLC

5847 / 5753

TICKET NUMBER 50045
LOCATION BHawg, KS
FOREMAN Casey Kennedy

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice # 807697

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6/6/16	4015	Gallagher # P-2	NW 26	17	21	MI
CUSTOMER JTC Oil Inc.			TRUCK #			
MAILING ADDRESS 35790 Plum Creek			DRIVER			
CITY Osawatomie		STATE KS	ZIP CODE 66064	TRUCK #		
			DRIVER			

TRUCK #	DRIVER	TRUCK #	DRIVER
729	Car Ken	✓	Safety Meeting
467	Kei Car	✓	
503	Har Bec	✓	
369	Mikhaa	✓	

JOB TYPE logstring HOLE SIZE 6 3/4" HOLE DEPTH 520' CASING SIZE & WEIGHT 4 1/2"
CASING DEPTH 570' DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT 8.13 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 150 # gel followed by 5 bbls fresh water, mixed & pumped 65 sks Thixblend I cement w/ 1/4 # Floreal per sk, flushed pumped clean, pumped 4 1/2" rubber plug to casing TD w/ 8.13 bbls fresh water, cement to surface, pressured to 800 PSI, released pressure, shut in casing.

[Handwritten signature]

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	
CE0002	on lease	MILEAGE		
CE0711	1/2 min	for mileage	330.00	
WE0853	1 hr	DO Vac	100.00	
		trucks	1930.00	
		- 55%	1061.50	
		subtotal		808.50
CC5860	65 sks	Thixblend I cement	1625.00	
CC6075	16 #	Floreal	32.00	
CC5965	150 #	Gel	45.00	
CP8178	1	@ 4 1/2" rubber plug	75.00	
		materials	1777.00	
		- 55%	977.35	
		subtotal		779.65
		8%		
		SALES TAX		63.97
		ESTIMATED TOTAL		1732.12
				(2849.16)

AUTHORIZATION *[Signature]* TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.