



**CONSOLIDATED**  
Oil Well Services, LLC

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

5805 / 5751

TICKET NUMBER 50031  
LOCATION Ottawa, KS  
FOREMAN Casey Kennedy

**FIELD TICKET & TREATMENT REPORT  
CEMENT**

**INVOICE # 807695**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
6/6/16	405	Gallagher # I-2	NW26	17	21	M
CUSTOMER JTC Oil Inc.			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS 35790 Plum Creek			729	Carson	✓ Safety Meeting	
CITY STATE ZIP CODE Ossawatimie KS 66064			467	KeiCar	✓	
			510	Ar/McD	✓	
			369	Mik Haa	✓	

JOB TYPE Longstring HOLE SIZE 5 7/8" HOLE DEPTH 500' CASING SIZE & WEIGHT 2 7/8"  
CASING DEPTH 473' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
DISPLACEMENT 2.73 bbls DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 4 bpm

REMARKS: field safety meeting, established circulation, mixed & pumped 150 #  
Gel followed by 5 bbls fresh water, mixed & pumped 65 stks Thixoblend  
I w/ 1/4 # Florenal per stk, cement to surface, flushed pump clean,  
pumped 2 1/2" rubber plug to casing TD w/ 2.73 bbls fresh water, took  
1500 PSI to pump plug, landed plug at 1700 PSI, well held pressure  
for 30 min MIT, released pressure, shut in casing.

*[Handwritten signature]*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0456	1	PUMP CHARGE	1500.00	
CE0002	on lease	MILEAGE		
CE0711	1/3 min	ten mileage	220.00	
WE0853	1 hr	80 Vac	100.00	
		trucks	1820.00	
		-55%	1001.00	
		Subtotal		819.00
CC5860	65 stks	Thixoblend I cement	1625.00	
CC6075	16 #	Florenal	32.00	
CC5965	150 #	Gel	45.00	
CP8176	1	2 7/8" Rubber plug	45.00	
		materials	1747.00	
		-55%	960.85	
		Subtotal		786.15
		8%		
		SALES TAX		62.89
		ESTIMATED TOTAL		1668.04

AUTHORIZATION *[Signature]* TITLE \_\_\_\_\_ DATE (3706.76)

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.