



6835  
6736

TICKET NUMBER 51603  
LOCATION Oakleyks  
FOREMAN Jerry

PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

FIELD TICKET & TREATMENT REPORT  
CEMENT **Invoice # 808811**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10-2-16	2777	Sewers 1-5	5	15S	34W	Logan
CUSTOMER Culbrea Th			Russell Spgs Sto Gold Etode deid Saccross pasture			
MAILING ADDRESS 3501 South Yale Avenue			TRUCK #	DRIVER	TRUCK #	DRIVER
CITY Tulsa			731	Cory D		
STATE OK			479	Cory D		
ZIP CODE 74135			772-7129	Walt D		

JOB TYPE 2 Stage HOLE SIZE 7 7/8 HOLE DEPTH 4650 CASING SIZE & WEIGHT 5 1/2 15.5#  
 CASING DEPTH 4644 DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER DV @ 2290  
 SLURRY WEIGHT 14.2/11.6 SLURRY VOL 1.42/1.9 WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING 44'  
 DISPLACEMENT 109/54 1/2 DISPLACEMENT PSI 1000# MIX PSI 1700# RATE \_\_\_\_\_

REMARKS: Safety meeting & rig upon Sec. thru wind run float eq. scratchers on 6, 7, 8, 9, 10, 11, 12, 110, 13, 14, 15 centralizers on 2, 4, 7, 9, 10, 12, 14, 17, 23, 52, baskets on 5, 24, 53, DV Tool (top of 53 set @ 2290 run casing to bottom pump ball thru & circ. vis & 36 pump 5 bbl H<sub>2</sub>O mix 500 gal mud flush pump 20 bbl KCL water mix 175 sks Thixobland III 5# Kol seal shut down release plug clean pump lines & displace 111 1/2 bbl (50 H<sub>2</sub>O 61 mud) Final lift 1000# plug landed 1700# released back & float held open tool @ 1000# & circulate 3 hrs mix 450 sks lite blend VII after 500 gal mud flush shut down release plug clean pump lines displace with 55 bbl H<sub>2</sub>O 500# lift plug landed & tool closed @ 1100# released back & float held put cement to pit  
 20 sks mouse hole 30 sks Rat hole Cement Circulated  
 Thank you  
 Jerry & crew

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0454	1	PUMP CHARGE	3900 <sup>00</sup>	3900 <sup>00</sup>
CE0062	30	MILEAGE	7 <sup>15</sup>	214 <sup>50</sup>
CE0710	29.73	ton mileage delivery	175	1570 <sup>88</sup>
CC5862	175 sks	Thixobland III	26 <sup>00</sup>	4550 <sup>00</sup>
CC6077	875 #	Kol seal	50	4375 <sup>00</sup>
CC5831	500 sks	lite blend VII	175 <sup>00</sup>	8750 <sup>00</sup>
CC6075	125 #	flow seal	3 <sup>00</sup>	375 <sup>00</sup>
CC6125	1000 gal	mud flush	65	6500 <sup>00</sup>
CC5300	2 gal	KCL	39 <sup>00</sup>	78 <sup>00</sup>
CP8485	1	5 1/2 APU Flat shoe	585 <sup>00</sup>	585 <sup>00</sup>
CP8254	1	5 1/2 latchdown assy	400 <sup>00</sup>	400 <sup>00</sup>
CP8554	10	5 1/2 centralizers	81 <sup>00</sup>	810 <sup>00</sup>
CP8629	3	5 1/2 baskets	385 <sup>00</sup>	1155 <sup>00</sup>
CP8676	40	5 1/2 scratchers	75 <sup>00</sup>	3000 <sup>00</sup>
CP8801	1	5 1/2 DV Tool	5970 <sup>00</sup>	5970 <sup>00</sup>
			Subtotal	32435.88
			-45%	14596.15
			Subtotal	17839.73
			SALES TAX	1177.47
			ESTIMATED TOTAL	19,017.20

Ravin 3737

AUTHORIZATION [Signature] TITLE \_\_\_\_\_ DATE \_\_\_\_\_

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.