



BASIC
ENERGY SERVICES

COPY

PAGE 1 of 1	CUST NO 1002661	YARD # 1718	INVOICE DATE 07/23/2018
INVOICE NUMBER 92761783			

Pratt (620) 672-1201
 B MC COY PETROLEUM CORP
 L PO Box: 39
 L SPIVEY
 T KS US 67142
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME O'Brate-UMCC
 O LOCATION
 B COUNTY Meade
 S STATE KS **INTERMEDIATE**
 I JOB DESCRIPTION **Cement-New Well Casing/Pi**
 E JOB CONTACT

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41121614	19570		Net - 30 days	08/22/2018

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 07/21/2018 to 07/21/2018</i>				
0041121614				
171815855L Cement-New Well Casing/Pi 07/21/2018 Cement/Surface Casing				
Premium/Common	270.00	EA		
C-17	127.00	LB		
Celloflake	68.00	EA		
"Top Rubber Cmt Plug, 7""	1.00	EA		
"7"" Float Shoe(Blue)"	1.00	EA		
"7"" Float Collar(Blue)"	1.00	EA		
"Centralizer, 7"" (Blue)"	6.00	EA		
Straight Vain Turbolator w/set screw	9.00	EA		
Industrial Rubber Thread Lock Kit	2.00	EA		
Mud Flush	840.00	EA		
Heavy Equipment Mileage	100.00	MI		
Blending & Mixing Service Charge	270.00	BAG		
Proppant & Bulk Del. Chgs., per ton mil	635.00	EA		
Depth Charge; 5001-6000'	1.00	EA		
Plug Container Util. Chg.	1.00	EA		
"Unit Mileage Chg (PU, cars one way)"	50.00	MI		
"Service Supervisor, first 8 hrs on loc.	1.00	EA		
Cement Data Acquisition Monitor	1.00	EA		

PLEASE REMIT TO: BASIC ENERGY SERVICES, LP
 PO BOX 841903
 DALLAS, TX 75284-1903

SEND OTHER CORRESPONDENCE TO:
 BASIC ENERGY SERVICES, LP
 801 CHERRY ST, STE 2100
 FORT WORTH, TX 76102

SUB TO
 INVOICE TO

DC



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING Job Log

Customer:	McCoy Petroleum Corp.	Cement Pump No.:	38119-19570 8 HRS	Operator TRK No.:	96815
Address:		Ticket #:	1718-15855 L	Bulk TRK No.:	30463-37547
City, State, Zip:		Job Type:	Z42- Cement Surface Casing INTERMEDIATE		
Service District:		Well Type:	OIL		
Well Name and No.:	O'Brate-UMCC	Well Location:	17,30,30	County:	Meade State: Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
PREMIUM	270	.5%C-17, 1/4#POLYFLAKE	30463-37547	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	15.6	1.18	5.18	318.6	Man Hours:	47
Tail:					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLs)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
0:00							ON LOC, SAFTEY MTG, R.U.
9:38						5400	TEST LINES
9:41 AM	4.8	20				290	PUMP MUD FLUSH
9:45 AM	5	5				290	H2O SPACER
9:47 AM	7					480	START MIXING @ 15.6#
10:00		57					SHUT DOWN, DROP PLUG
10:01	7					170	START DISPLACEMENT, WASHUP ON PLUG
10:37 AM	3	206				830	SLOW RATE
10:42		216				1000-1500	PLUG DOWN
10:45						1500-0	RELEASE PSI, FLOAT HELD
10:47						1600	TEST CASING
11:02						1580-0	RELEASE PSI, FLOAT HELD
							JOB COMPLETE
							THANK YOU FOR YOUR BUSINESS!!!!

Size Hole	8 3/4	Depth	5693'		TYPE	
Size & Wt. Csg.	7 26#	Depth	5686.04'	New / Used	Packer	Depth
tbg.		Depth		SHOE JT	42.44'	Retainer
Top Plugs		Type				Perfs

Customer Signature:	Basic Representative:	CHAD HINZ
	Basic Signature:	
	Date of Service:	7/21/2018