

Dale Jackson Production Co
Box 266, Mound City, Ks 66056



Cell # 620-363-2683

Office # 620-363-2696

Surface: 20' of 6"	Cemented: 5 Sacks	Hole Size: 8 3/4"
Long string: 678' of 2 7/8 8 round	Cemented: 95 sacks	Hole Size: 5 5/8"
SN: 686'	Packer: -	
Plugged: -	Bottom Plug: -	
TD: 681'		
Lease:	McCann	
Owner:	Bobcat Oilfield Services Inc	
OPR #:	3895	
Contractor:	DALE JACKSON PRODUCTION CO.	
OPR #:	4339	

Well Log

Well #: 42
Location: NW,NE,SW,NE, S30-T16-R22E
County: Miami
FSL: 3680'
FEL: 1724'
API#: 15-121-31527-00-00
Started: 11-19-18
Completed: 11-19-18

TKN	BTM Depth	Formation	TKN	BTM Depth	Formation
1	1	Top Soil	16	573	Shale
10	11	Clay	3	576	Coal
1	12	Black Shale	4	580	Lime
14	26	Lime	1	581	Shale
7	33	Sandy Shale	5	586	Oil Sand (fair bleed)
17	50	Lime	2	588	Oil Sand (very shaley)
5	55	Shale	7	595	Black Shale
3	58	Red Bed	9	604	Lime
22	80	Shale	2	606	Coal
15	95	Lime	7	613	Light Shale
2	97	Black Shale	13	626	Shale
33	130	Sandy Shale	5	631	Lime
55	185	Shale	5	636	Shale
19	204	Lime	2	638	Black Shale
17	221	Sandy Shale	6	644	Shale
14	235	Light Shale	2	646	Lime
3	238	Lime	1	647	Shale
22	260	Shale	3	650	Oil Sand (very shaley) (poor bleed)
1	261	Red Bed	2	652	Oil Sand (good bleed)
9	270	Shale	1	653	Oil Sand (some shale) (fair bleed)
17	287	Lime	3	656	Oil Sand (fair bleed)
13	300	Shale	2	658	Oil Sand (good bleed)
24	324	Lime	3	661	Oil Sand (very shaley)
5	329	Black Shale	2	663	Oil Sand (some shale) (fair bleed)
7	336	Shale	2	665	Sandy Shale
18	354	Lime	TD	681	Shale
5	359	Black Shale			
14	373	Lime			
22	395	Shale			
5	400	Sandy Shale			
73	473	Shale			
4	477	Sandy Shale (odor)			
3	480	Oil Sand (shaley) (poor bleed)			
30	510	Shale			
5	515	Red Bed			
4	519	Light Shale			
10	529	Light Shale (limey)			Surface 11-14-18, Set time 2:00pm
1	530	Oil Sand (some shale) (fair bleed)			Called 1:45, talked to Dallas
2	532	Oil Sand (good bleed)			Long string 678' 2 7/8', 11-19-18
3	535	Sandy Shale (oil sand strks)			Set time 2:30 pm, TD 681'
11	546	Lime			Called 1:45 pm, Talked to Brooke
8	554	Shale			
3	557	Lime			Corrected