

**SM Oil & Gas, Inc.**  
**P. O. Box 189**  
**Skiatook, Oklahoma 74070**  
620-725-3200

November 8, 2016

Kansas Corporation Commission  
Conservation Division  
266 N. Main Street – Suite #220  
Wichita, Kansas 67202-1513


**Re: Fulsom B #13-1**  
**API #15-019-27549-00-00**  
**Cement Usage ACO-1**

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 10 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,



Thomas H. Oast  
Area Manager

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**

Ticket No. **3031**  
 Foreman Kevin McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-16-16	1180	Fulson B 13-1				Cq	Ks
Customer S. M. OIL & GAS, INC.			Safety Meeting KM DG RL ZA	Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 189				105	DAVE G.		
City SKIATOOK				112	RICK C		
State OK				114	Zevi A		
Zip Code 74070							

Job Type Longstring Hole Depth 2131' Slurry Vol. 46 Lead 24 Tail Tubing \_\_\_\_\_  
 Casing Depth 2119' Hole Size 6 3/4" Slurry Wt. 12.8 - 14\*\* Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 11.60" Cement Left in Casing 0' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 34.6 BBL Displacement PSI 1000 Bump Plug to 1400 PSI BPM \_\_\_\_\_

Remarks: Safety Meeting: Rig up to 4 1/2 casing. BREAK CIRCULATION w/ 50 BBL FRESH WATER. Pump 500\* GEL Flush w/ HULLS, 10 BBL WATER SPACER, MIXED 160 SKS 50/50 Pozmix Cement w/ 6% GEL 1\* PhenoSeal/SK @ 12.8\*/gal yield 1.61 = 46 BBL SLURRY, TAIL IN w/ 100 SKS OWC Cement w/ 1\* PhenoSeal/SK @ 14\*/gal = 24 BBL SLURRY. WASH OUT Pump & Lines. Shut down. Release Plug. Displace Plug to SEAT w/ 34.6 BBL FRESH WATER. FINAL Pumping Pressure 1000 PSI. Bump Plug to 1400 PSI. WAIT 2 mins. Release Pressure. Float Held. Shut in @ 0 PSI. Good Cement RETURNS to SURFACE = 12 BBL SLURRY to Pit. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	160 SKS	50/50 Pozmix Cement	11.25	1800.00
C 206	800 *	Gel 6% } Lead Cement	.20 *	160.00
C 208	160 *	PhenoSeal 1*/SK	1.25 *	200.00
C 202	100 SKS	OWC Cement } TAIL Cement	19.15	1915.00
C 208	100 *	PhenoSeal 1*/SK	1.25	125.00
C 206	500 *	Gel Flush	.20 *	100.00
C 214	40	Hulls	.45 *	18.00
C 108 A	11.92 TONS	BULK TRUCKS x 2	M/c	690.00
C 113	3 HRS	100 BBL VAC TRUCK (C&E OIL)	85.00	255.00
C 224	4200 gals	City water	10.00/1000	42.00
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
			Sub Total	6518.50
			Less 5%	344.65
			8.5% Sales Tax	374.43
			Total	6548.28

Authorization Tony [Signature] Title \_\_\_\_\_

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.