

SM Oil & Gas, Inc.
P. O. Box 189
Skiatook, Oklahoma 74070
620-725-3200

November 21, 2016

Kansas Corporation Commission
Conservation Division
266 N. Main Street – Suite #220
Wichita, Kansas 67202-1513

Re: Fulsom "B" #9-2
API #15-019-27570-00-00
Cement Usage ACO-1

To Whom It May Concern:

SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 10 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.

An invoice showing the bulk quantity of cement is available if needed.

Thank you,



Thomas H. Oast
Area Manager

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **3064**
 Foreman Russell McCloy
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-29-16	1180	Fulsom B9-2				CQ	KS
Customer S.M. Oil + Gas Inc.			Safety Meeting Rm ALAN Steve Zev:	Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 189				104	ALAN M		
City Skiatook				110	STEVE		
State OK				112	ZEV		
Zip Code 74070							

Job Type Longstring Hole Depth _____ Slurry Vol. _____ Tubing _____
 Casing Depth _____ Hole Size _____ Slurry Wt. _____ Drill Pipe _____
 Casing Size & Wt. 4 1/2 Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting, Rig up to 4'1/2 wash Down 1' to T.D. BLEED OF AIR. Double clamp 4 1/2 to be 1' off Bottom. Mix + Pump 500# Gel w/ Hulls 5 Bbl spacer. Rig up cement Head. Break circulation w/ 3 Bbl water mix + Pump 135 SKs 50/50 Pozmix w/ 6% Gel 1# Phenoseal at 12.8" = 36 1/2 Bbl slurry TAIL w/ 75 SKs owc cement w/ 1# Phenoseal w/ yield 1.5 = 20 Bbl slurry, wash out Pump + Lines. Release 4 1/2 TOP Rubber Plug Displace w/ 25 1/2 Bbl water Final Pump PSI 800# Bump Plug to 1350# check float float held. 13 Bbl cement slurry to surface. close up flow ditch Annulus Full of cement. Job complete TEAR DOWN

Thank you
 Russ + crew

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C-102	1	Pump Charge	1050.00	1050.00
C-107	30	Mileage	3.95	118.50
C-204	135	SKs 50/50 Pozmix	11.25	1518.75
C-206	680#	Gel = 6% } HEAD cement	.20	136.00
C-208	135#	Phenoseal 1# per/sk } HEAD cement	1.25	168.75
C-202	75	SKs owc cement	19.15	1436.25
C-208	75#	Phenoseal = 1# per/sk } TAIL cement	1.25	93.75
C-206	500#	Gel Flush	.20	100.00
C-214	40#	Hulls	.45	18.00
C-108 A	9.57	Tow mileage Bulk Truck x 2	mic	690.00
C-403	1	4 1/2 TOP Rubber Plug	45.00	45.00
C-113	3 hr	80 Bbl vac Truck (C+E)	85.00	255.00
C-224	3,300	gallons city water	10 per hour	33.00
				5,663.00
Thank you!				298.24
				8.5%
				Sales Tax
				301.71

Authorization (Witnessed) by JOEL Title co/owner Total 5,666.47

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.