

**SM Oil & Gas, Inc.**  
**P. O. Box 189**  
**Skiatook, Oklahoma 74070**  
620-725-3200

November 29, 2016

*Kansas Corporation Commission  
Conservation Division  
266 N. Main Street – Suite #220  
Wichita, Kansas 67202-1513*

**Re: Fulsom "B" #13-2**  
**API #15-019-27571-00-00**  
**Cement Usage ACO-1**

To Whom It May Concern:

*SM Oil & Gas, Inc. buys quantities of Portland Type I cement, which comes on pallets of 35 sacks per pallet, for the companies usage. In this case, the required 10 sacks of cement were mixed by our own drilling rig personnel and used to properly install the surface casing.*

*An invoice showing the bulk quantity of cement is available if needed.*

Thank you,



Thomas H. Oast  
Area Manager

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **3054**  
 Foreman KEVIN MCCOY  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
12-5-16	1180	Fulsom B 13-2				CQ	KS	
Customer S. M. OIL & GAS, INC			Safety Meeting KM AB RM AM RL		Unit #	Driver	Unit #	Driver
Mailing Address P.O. Box 189					105	ALLEN B.		
City SKIATOOK			State OK		110	Russ M.		
Zip Code 74070					112	ALAN M.		
					141	RICK L.		

Job Type Longstring Hole Depth 1630' Slurry Vol. 36 BBL LEAD Tubing \_\_\_\_\_  
20 BBL TAIL  
 Casing Depth 1622' Hole Size 6 3/4" Slurry Wt. 12.8 - 14" Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 4 1/2 11.60" Cement Left in Casing 0' Water Gal/SK \_\_\_\_\_ Other \_\_\_\_\_  
 Displacement 25.5 BBL Displacement PSI 750 Bump Plug to 1400 PSI BPM \_\_\_\_\_

Remarks: Safety Meeting: Rig up to 4 1/2 casing w/ wash head. BREAK CIRCULATION w/ 40 BBL fresh water. wash down 10' 4 1/2. Pump 500 \* Gel Flush w/ HULLS, 5 BBL water SPACER. Shut down, Rig up Cement Head. MIXED 135 SKS 50/50 Pozmix Cement w/ 6% Gel, 1\*PhenoSeal/SK @ 12.8"/gal, yield 1.50 = 36 BBL slurry, TAIL in w/ 75 SKS owc Cement w/ 1\*PhenoSeal/SK @ 14"/gal, yield 1.50 = 20 BBL slurry. wash out Pump & Lines, shut down, Release Plug. Displace Plug to Seat w/ 25.5 BBL fresh water. FINAL Pumping Pressure 750 PSI. Bump Plug to 1400 PSI. wait 2 mins. Release Pressure. Float Held. Shut in @ 0 PSI. Good Cement Returns to SURFACE = 16 BBL slurry to Pit. Job Complete. Rig Down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1050.00	1050.00
C 107	30	Mileage	3.95	118.50
C 204	135 SKS	50/50 Pozmix Cement	11.25	1518.75
C 206	680 *	Gel 6%	.20 *	136.00
C 208	135 *	PhenoSeal 1#/SK	1.25 *	168.75
C 202	75 SKS	OWC Cement	19.15	1436.25
C 208	75 *	PhenoSeal 1#/SK	1.25 *	93.75
C 206	500 *	Gel Flush	.20 *	100.00
C 214	40 *	HULLS	.45 *	18.00
C 108 A	9.57 Tons	Ton Mileage Bulk Trucks X 2	M/C	690.00
C 403	1	4 1/2 Top Rubber Plug	45.00	45.00
C 113	3 Hrs	80 BBL VAC TRUCK	85.00	255.00
C 224	3300 gals	City water	10.00/1000	33.00
			Sub TOTAL	5663.00
			Less 5%	298.24
			8.5% Sales Tax	301.71
				5666.47

Authorization [Signature] Title \_\_\_\_\_

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.