



# RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

## Brewer 1-A

			Start 12-11-18
			Finish 12-13-18
9	soil	9	
22	clay/gravel	31	
63	shale	94	
76	lime	170	
102	shale	272	
132	lime	404	
26	shale	430	
67	lime	497	Set 40' of 7" w/ 5sxs
11	shale	508	Ran 970' of 2 7/8
47	lime	555	cemented to surface 125sxs
181	shale	736	
30	lime	766	
47	shale	813	
36	lime	849	
15	shale	864	
7	lime	871	
10	shale	881	
8	lime	889	
11	shale	900	
4	lime	904	
32	shale	936	
5	Sandy shale	941	odor
9	bkn sand	950	good show
26	Shale	976	T.D.