



# RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

## Brewer 4-1

			Start 12-13-18
			Finish 12-17-18
9	soil	9	
23	clay/gravel	32	
65	shale	97	
80	lime	177	
98	shale	275	
128	lime	403	
27	shale	430	
68	lime	498	Set 40' of 7" w/ 5sxs
9	shale	507	Ran 968.6' of 2 7/8
48	lime	555	cemented to surface 125sxs
181	shale	736	
30	lime	766	
48	shale	814	
36	lime	850	
15	shale	865	
6	lime	871	
15	shale	886	
4	lime	890	
11	shale	901	
2	lime	903	
34	shale	937	
5	Sandy shale	942	odor
10	bkn sand	952	good show
22	Shale	974	T.D.