



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

TICKET NUMBER 54220
 LOCATION El Dorado, KS
 FOREMAN Brad Butler - Austin

FIELD TICKET & TREATMENT REPORT
CEMENT

Long string

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9-11-18	3631	Sabin B #14	13	23s	14w	Reno
CUSTOMER Howell Oil Co.			TRUCK #		DRIVER	
MAILING ADDRESS 2400 Riverbirch Rd.			603		Austin	
CITY Hutchinson			713		Brad	
STATE Ks			702		James	
ZIP CODE 67502						

JOB TYPE LongString HOLE SIZE 7 7/8" HOLE DEPTH 3500 TB CASING SIZE & WEIGHT 5 1/2" - 15.5 lb.
 CASING DEPTH 3482' DRILL PIPE _____ TUBING _____ OTHER 14' Landing JOINT
 SLURRY WEIGHT 13.8 to 14.0 SLURRY VOL. 65 WATER gal/sk _____ CEMENT LEFT in CASING 2'
 DISPLACEMENT 83 Bbls DISPLACEMENT PSI 950 MIX PSI _____ RATE 5.5 bpm.

REMARKS: Safety Meeting: Rig up to 5 1/2" casing, pumped 10 Bbls water ahead.
Mixed 200 Ks Thixo Blend III along with KOI-SEAL 5 lb per/sk and Pheno-SEAL 1/2 lb per/sk at 14 lb per/gal.
Shut down - wash out pump & lines - Release Plug, displace Plug with 83 Bbls water.
Start pumping at 950 psi. - Land Plug with 1500 psi - wait a few minutes - Release Pressure
Float Held - close casing in w/ Opsi. We had good returns during cementing procedure
Job complete - Teardown

"Thank you"

NOTE: Plugged R.H. with 30 sacks cement and M.H. with 20 sacks cement

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0452	1	PUMP CHARGE	2300.00	2300.00
CE0002	60	MILEAGE	7.15	429.00
CE0710	825 Tm	Bulk Truck Delivery charge	1.75	1443.75
CC5862	250 SACKS	Thixo Blend III	26.00	6500.00
CC6077	1250 lbs.	KOI-SEAL 5 lb per/sk	.50	625.00
CC6079	120 lbs.	Pheno-SEAL 1/2 lb per/sk	1.35	162.00
CP8254	1	5 1/2" Latch Down Plug & Assembly	400.00	400.00
CP8485	1	5 1/2" Float Shoe - AFU	585.00	585.00
CP8576	8	5 1/2" Turbolizers	110.00	880.00
CP8651	3	5 1/2" Cement Baskets - Reciprocating	360.00	1080.00
				14404.75
		Discount		-5041.66
		Sub Total		9363.09

SALES TAX _____
 ESTIMATED TOTAL _____
 AUTHORIZATION [Signature] TITLE Foreman DATE 9-10-18

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

TICKET NUMBER 54567

LOCATION Eldorado 125

FOREMAN Austin

FIELD TICKET & TREATMENT REPORT
CEMENT

Conductor

DATE	CUSTOMER #	WELL NAME & NUMBER		SECTION	TOWNSHIP	RANGE	COUNTY
9-5-18		Sabin 3 #14		13	23	14	Reno
CUSTOMER				TRUCK #			
Howell oil Co				868			
MAILING ADDRESS				DRIVER			
2400 Riverbriar RD				Austin			
CITY		STATE	ZIP CODE	TRUCK #			
Hutchinson		KS	67502	446			
				DRIVER			
				Jude			
				TRUCK #			
				413			
				DRIVER			
				JAMES			

JOB TYPE Surface HOLE SIZE 17 1/2 HOLE DEPTH 316 CASING SIZE & WEIGHT 13 3/8 - 48
 CASING DEPTH 296 DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT 14.5 SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 46.5 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: *Safety meeting. Hooked up to 13 3/8 Surface broke circulation then pumped 5 bbl water then pumped 250 sks cement then displaced 47 bbl water put around 19 bbl to the pit.*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	1500.00
CE0002	60	MILEAGE	7.15	429.00
CE0710	11.75	ton mileage	1.75	1233.75
CC5871	250	Surface blend II	23.00	5750.00
CC6075	125	Poly flake	7.00	250.00
				9162.75
				3206.96
			SALES TAX	
			ESTIMATED TOTAL	5955.78

Ravin 3737
 AUTHORIZATION *[Signature]* TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.