

JOB LOG

2 pages

SWIFT Services, Inc.

DATE 2-6-19 PAGE NO.

CUSTOMER *Venture Resources* WELL NO. *#1 SWD* LEASE *Myrtel Cross* JOB TYPE *RTA* TICKET NO. *27458*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	<i>1030</i>							<i>On location 2 1/2 x 7" Tubing @ 3850'</i>
		<i>5</i>	<i>10</i>			<i>600</i>		<i>Pump wtr to make sure tubing is clear</i>
		<i>5</i>	<i>25 8.5</i>			<i>600</i>		<i>Pump CMT - 125 sks @ 15.5 <sup>ppg</sup> Disp - Circulated out 7"  Job Complete</i>
								<i>Thanks Dustin, Zach &amp; Isaac</i>

JOB LOG

#1 SWD

SWIFT Services, Inc.

DATE  
2-8-19

PAGE NO.

CUSTOMER  
Venture Resources

WELL NO.  
~~XXXXXXXXXX~~

LEASE  
Myrtle Cross

JOB TYPE  
PTA

TICKET NO.  
27459

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1100							On location
								7" inside 10 3/4" perfs - 1250 & 1650 Tagged plug @ 2565'
		5	10			400		1st Plug @ 2530' 150 sks cmt w/ 300 # Halls pump wtr spacer
		5	40			900		pump cmt @ 13.0 ppb
		5	5			900		Disp
		5	85			400		2nd Plug - 1650 325 sks cmt w/ 400 # Halls pump cmt
		1	0			0		- Circulated out 7" - Blowing out 10 3/4" Disp
								T.O.D.
								Hook up to 10 3/4" (JO) to circ out to 3/4"
		3	30			400 100		pump cmt 40 circ - 125 sks Shut in @ 100 psi
	1500							Job Complete
								Thanks David, ZACH & ISAAC