



1700 S. Country Estates Road
 Liberal, KS 67901
 PH (620)-624-2277 FAX (620) 624-2280

SERVICE ORDER - 1718 17205 L

TTL MHR 34

Date: 1/9/2019

Well Name: Martin-Peterson #1	Location: 16,29,41
County - State: Stanton, Ks	RRC #: 19919-4.5
Type Of Service: Z42 - Cement Plug to Abandon	Customer's Order #: 1004849

Customer: Western Operating

Address: 1165 Delaware Street Suite 200
 Denver Co. 80204

As a consideration, the above named Customer agrees to pay Basic Energy Services in accord with the rates and terms stated in Basic Energy Services current price lists. Invoices are payable NET 30 (SEE 10.2) after date of invoice. Upon Customer's default in payment of Customers account by such date, Customer agrees to pay interest thereon after default at 18% per annum. In the event it becomes necessary to employ an attorney to enforce collection of said account, Customer agrees to pay all the collection costs and attorney fees. These terms and conditions shall be governed by the laws of the state where services are performed or equipment or materials are furnished.

Basic Energy Services, warrants only title to the products, supplies and materials and that the same are free from defects in workmanship. THERE ARE NO WARRANTIES, EXPRESS OR IMPLIED, MERCHANTABILITY, FITNESS FOR A PARTICULAR PURPOSE OR OTHERWISE WHICH EXTEND BEYOND THOSE STATED IN THE IMMEDIATELY PRECEDING SENTENCE. Basic Energy Services, liability and Customer's exclusive remedy in any cause of action (whether in contract, tort, product liability, breach of warranty or otherwise) arising out of the sale or use of any products, supplies, or materials upon their return to Basic Energy Services, is expressly limited to the replacement of such products, supplies or materials or, at Basic Energy Services, option, to the allowance to the Customer of credit for the cost of such items. In no event shall Basic Energy Services be liable for special, indirect, punitive or consequential damages.

CODE	QTY	UOM	DESCRIPTION	PRICE	TOTAL	
CL103	170	Sk	50/40 POZ	12.00	2040.00	
CC200	294	Lb	Cement Gel	0.25	73.50	
E101	200	Mi	Heavy Equipment Mileage	7.50	1500.00	
CE240	170	Sk	Blending & Mbdng Service Charge	1.40	238.00	
E113	735	Tn/Mi	Proppant and Bulk Delivery Charges, per ton mile	2.50	1837.50	
CE202	1	4 Hrs	Depth Charge; 1001'-2000'	1500.00	1500.00	
E100	100	Mi	Unit Mileage Charge-Pickups, Small Vans & Cars (one way)	4.50	450.00	
S003	1	Ea	Service Supervisor, first 8 hrs on loc.	175.00	175.00	
T105	1	Ea	Cement Data Acquisition Monitor / Strip Chart Recorder	550.00	550.00	
					Book Total:	\$8,364.00
					Taxes:	
					Disc. Price:	\$5,018.40

PUMP TRUCK NUMBER: 38117, 19919

DRIVER: Sam Euler
 Daniel Bach
 BASIC ENERGY SERVICES

THIS JOB WAS SATISFACTORILY COMPLETED YES NO
 OPERATION OF EQUIPMENT WAS SATISFACTORY YES NO
 PERFORMANCE OF PERSONEL WAS SATISFACTORY YES NO
 X [Signature] CUSTOMER OR HIS AGENT

Customer Comments or Concerns:



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING Job Log

Customer:	Western Operating	Cement Pump No.:	38117, 19919 Hrs. 4.5	Operator TRK No.:	96816
Address:	1165 Delaware Street Suite 200	Ticket #:	1718 17205 L	Bulk TRK No.:	30464, 19578 Oscar
City, State, Zip:	Denver Co. 80204	Job Type:	Z42 - Cement Plug to Abandon		
Service District:	1718 - Liberal, Ks.	Well Type:	OIL		
Well Name and No.:	Martin-Peterson #1	Well Location:	16,29,41	County:	Stanton
				State:	Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
60/40 Poz	170	4% Total Gel	30464, 19578 Oscar	Front	Back
				Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	13.5	1.5	7.5	255	TT Man Hours:	34
Tail:					# of Men on Job:	3

Time (am/pm)	(BPM)	Volume (BBLS)	Pumps		Pressure (PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
13:15							ON LOCATION & SAFETY MEETING
13:30							RIG UP
2:45 PM	5	13.3 slurry				200	PUMP PLUG #1 @ 1680' 50SX @ 13.5#
2:52 PM		20.4					DISPLACE W/ 20.4BBL
2:54 PM							SHUTDOWN
15:44	5	13.3 slurry				190	PUMP PLUG #2 @ 710' 50SX @ 13.5#
15:47		6.6					DISPLACE W/ 6.6BBL
3:48 PM							SHUTDOWN
15:48		5.3 slurry					PUMP PLUG #3 @ 60' TO SURFACE 20SX @ 13.5#
15:50							SHUTDOWN
16:15		13.3 slurry					PLUG RAT & MOUSE W/ 50SX
16:45							SHUTDOWN
							JOB COMPLETE

Size Hole	7 7/8"	Depth		TYPE		Swage	
Drill Pipe	4 1/2" 16.6#	Depth		New / Used	Packer	Depth	
tbg.		Depth			Retainer	Depth	
Plugs	1680'	710'	60'	Rat & Mouse	Perfs	CIBP	

Customer Signature:	Basic Representative:	Daniel Beck
	Basic Signature:	<i>Daniel Beck</i>
	Date of Service:	1/9/2019

Western Operating Martin-Peterson #1

