



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

111606
11849

TICKET NUMBER 55461
LOCATION Ottawa, KS
FOREMAN Cases, Kennedy

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice # 814200

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9/21/18	4807	Reyn # LO-22	NE 21	30	16	WL
CUSTOMER Lakeshore Operating LLC						
MAILING ADDRESS 340 S. Laura						
CITY Wichita		STATE KS	ZIP CODE 67211			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			729	Cas Ken	✓ Safety	Maeting
			495	Kei Car	✓	
			504	Ala Mad	✓	
			675	Kei Det	✓	

JOB TYPE long string HOLE SIZE 5 5/8" HOLE DEPTH 982' CASING SIZE & WEIGHT 2 7/8" EUE
CASING DEPTH 974' DRILL PIPE _____ TUBING _____ OTHER _____
SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
DISPLACEMENT 5.64 lbs DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety maeting, established circulation, mixed + pumped 100# Gel followed by 5 bbls fresh water, mixed + pumped 105 SFS Pozblend IIA cement w/ 2% gel, 5# Kalseal, + 1# Phenoseal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 5.64 lbs fresh water, pressured to 800 PSI, released pressure to set float valve.

Handwritten signature/initials

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	
CE0002	55 mi	MILEAGE	393.25	
CE0711	1/2 min	ton mileage	330.00	
WE0853	3 hrs	80 Uac	300.00	
		trucks	2523.25	
		- 35%	883.14	
		subtotal		1640.11
181166 CC5842	105 SFS	Pozblend IIA cement	1548.75	
CC5965	281 #	Gel	84.30	
CC6077	525 #	Kalseal	262.50	
CC6079	105 #	Phenoseal	141.75	
CP8176	1	2 1/2" rubber plug	45.00	
		materials	2682.30	
		- 35%	728.81	
		subtotal		1353.49
		SALES TAX 6.5%		87.98
		ESTIMATED TOTAL		3081.60
				(4740.90)

SCANNED

AUTHORIZATION [Signature] TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.