



PRESSURE PUMPING LLC  
PO Box 884, Chanute, KS 66720  
620-431-9210 or 800-467-8676

11667  
11SSO

TICKET NUMBER 55462  
LOCATION Ottawa, KS  
FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT  
CEMENT

Invoice # 814201

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
9/21/18	4807	Fuller # LO-63	NW 33	23	16	WO
CUSTOMER <u>Lakeshore Operating LLC</u>						
MAILING ADDRESS <u>340 S. Laura</u>						
CITY <u>Wichita</u>		STATE <u>KS</u>	ZIP CODE <u>67211</u>			
			TRUCK #	DRIVER	TRUCK #	DRIVER
			729	Cas Ken	✓ Safety Meeting	
			495	Kei Car	✓	
			804	Alamad	✓	
			675	Kei Det	✓	

JOB TYPE Long string HOLE SIZE 5 7/8" HOLE DEPTH 1147' CASING SIZE & WEIGHT 2 7/8" EUE  
 CASING DEPTH 9140' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT 6.60 bbls DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 100# Gel followed by 5 bbls fresh water mixed + pumped 151 sks Pozblend II A cement w/ 2% gel, 5# Kalseal, + 1# Phenoseal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 6.60 bbls fresh water, pressured to 800 PSI, released pressure to set float valve.

*Handwritten signature*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	
CE0002	40 mi	MILEAGE	286.00	
CE0711	1/2 min	for mileage	330.00	
WE0853	3 hrs	80.00/hr	300.00	
		trucks	2416.00	
		- 35%	845.60	
		subtotal		1570.40
18167 CC5842	151 sks	Pozblend II A cement	2227.25	
CC5865	360 #	Gel	108.00	
CC6077	755 #	Kalseal	377.50	
CC6079	151 #	Phenoseal	203.85	
CD8176	1	2 1/2" rubber plug	45.00	
		materials	2961.60	
		- 35%	1036.56	
		subtotal		1925.04
<b>SCANNED</b>				
		7.5%	SALES TAX	144.38
			ESTIMATED TOTAL	3639.82

AUTHORIZATION [Signature] TITLE \_\_\_\_\_ DATE (5599.72)

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.