

Elite Cementing & Acidizing of KS, LLC
 810 E 7th, PO Box 92
 Eureka, KS 67045



Date	Invoice #
10/29/2018	4197

Bill To	
Drake Exploration c/o Darrel Walters PO Box 782228 Wichita, KS 67278-2228	
Customer ID#	1012

Job Date	10/25/2018
Lease Information	
Hills #1 OWWO	
County	Sumner
Foreman	KM

Item	Description	Qty	Rate	Amount
C102	Cement Pump-Longstring	1	1,100.00	1,100.00
C107	Pump Truck Mileage (one way)	60	4.20	252.00
C201	Thick Set Cement	160	20.50	3,280.00T
C207	KolSeal	800	0.47	376.00T
C208	Pheno Seal	160	1.30	208.00T
C108B	Ton Mileage-per mile (one way)	528	1.40	739.20
C420	4 1/2" Latch Down Plug	1	210.00	210.00T
C760	4 1/2" Type B Basket Shoe	1	1,060.00	1,060.00T
C680	4 1/2" Float Collar Body Only	1	194.00	194.00T
C603	4 1/2" Cement Basket	1	214.00	214.00T
C503	4 1/2" Centralizer	4	46.00	184.00T
C222	KCL	3	30.00	90.00T
D101	Discount on Services		-104.56	-104.56
D102	Discount on Materials		-290.80	-290.80T

We appreciate your business!

Phone #	Fax #	E-mail
620-583-5561	620-583-5524	rene@elitecementing.com

Send payment to:
 Elite Cementing & Acidizing of KS, LLC
 PO Box 92
 Eureka, KS 67045

Subtotal	\$7,511.84
Sales Tax (7.5%)	\$414.39
Total	\$7,926.23
Payments/Credits	\$0.00
Balance Due	\$7,926.23

810 E 7TH
PO Box 92
EUREKA, KS 67045
(620) 583-5561



Cement or Acid Field Report

Ticket No. **4197**
Foreman Kevin McCoy
Camp EUREKA

API # 15-191-00379-00-01

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
10-25-18	1012	HILLS #1 OWWO	10	34S	2E	Sumner	Ks
Customer <u>Drake Exploration, LLC</u>			Safety Meeting KM AM CG	Unit #	Driver	Unit #	Driver
Mailing Address <u>P.O. Box 782228</u>				104	ALAN M.		
City <u>Wichita</u>				115	CALEB G		
State <u>Ks</u>		Zip Code <u>67278</u>					

Job Type Longstring Hole Depth _____ Slurry Vol. 41 BBL 4/5 Tubing _____
 Casing Depth 2902' Hole Size 7 7/8" Slurry Wt. 13.8* Drill Pipe _____
 Casing Size & Wt. 4 1/2 9.5* Cement Left in Casing 3.75' Water Gal/SK 9.0 Other _____
 Displacement 47.5 Displacement PSI 700 Bump Plug to 1200 PSI BPM _____

Remarks: Safety Meeting: Rig up to 4 1/2 casing w/ Basket Shoe Set @ 2902' G.L. Drop BRASS TRIP BALL. Set Basket Shoe @ 750 PSI. Pump 15 BBL Fresh water. Mixed 125 SKS THICK Set Cement w/ 5* KOL-SEAL /SK, 2* Pheno. SEAL /SK @ 13.8*/GAL, yield 1.85 = 41 BBL SLURRY. Wash out Pump & Lines. Shut down. Release Latch down Plug. Displace Plug to Seat w/ 47.5 BBL Fresh water. (KOL in first 20 BBL) Final Pumping Pressure 700 PSI. Bump Plug to 1200 PSI. Wait 2 mins. Release Pressure. Float & Plug Held. Good Circulation @ ALL times while Cementing. Job Complete. Rig down.

Plug Rate Note 20 SKS, Mouse Hole 15 SKS

Centralizers on #1, 2, 3, 4. Cement Basket @ 317' Below Surface

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 102	1	Pump Charge	1100.00	1100.00
C 107	60	Mileage	4.20	252.00
C 201	160 SKS	THICK Set Cement	20.50	3280.00
C 207	800 *	KOL-SEAL 5*/SK	.47 *	376.00
C 208	160 *	Pheno. SEAL 1*/SK	1.30 *	208.00
C108 B	8.8 TONS	Ton Mileage 60 miles	1.40	739.20
C 420	1	4 1/2 Latch down Plug	210.00	210.00
C 760	1	4 1/2 Type "B" BASKET Shoe w/ FLOAT	1060.00	1060.00
C 680	1	4 1/2 FLOAT COLLAR Body Only	194.00	194.00
C 603	1	4 1/2 Cement BASKET	214.00	214.00
C 503	4	4 1/2 x 7 7/8 Centralizers	46.00	184.00
C 222	3 gals	KOL (IN FIRST 20 BBLs OF Displacement water)	30.00	90.00
			Sub Total	7907.20
			Less 5%	417.17
			7.5% Sales Tax	436.20
Authorization <u>Witnessed By DARRIN Broyles Title OWNER</u>			Total	7926.23

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.