



PRESSURE PUMPING LLC
 PO Box 884, Chanute, KS 66720
 620-431-9210 or 800-467-8676

11799
 11679

TICKET NUMBER 55491
 LOCATION Ottawa, KS
 FOREMAN Casey Kennedy

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice # 814336

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10/9/18	4807	Renn # LO-SWD-1	NE 21	30	16	WL
CUSTOMER Lakeshore Operating LLC			TRUCK # DRIVER TRUCK # DRIVER			
MAILING ADDRESS 340 S. Laura			729	CarKen	✓	Safety Meeting
CITY STATE ZIP CODE Wichita KS 67211			467	Kei Car	✓	
			804	HarBec	✓	
			675	KeiDet	✓	

JOB TYPE long string HOLE SIZE 5 5/8" HOLE DEPTH 1203' CASING SIZE & WEIGHT 2 7/8"
 CASING DEPTH 1198' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 6.93 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed + pumped 200# Gel followed by 5 bbls fresh water, mixed + pumped 147 stks Pozblend II cement w/ 2% gel, 5# Kalseal, + 1# Phenoseal per stk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 6.93 bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MIT, released pressure to set float valve.

[Handwritten signature]

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	✓
CE0002	55 mi	MILEAGE	393.25	✓
CE0711	min	tax mileage	660.00	✓
WE0853	5 hrs	80 Vac	500.00	✓
		trucks	3053.25	
		-30%	915.98	
		Subtotal		2137.27
CC5842	147 stks	Pozblend II A cement	2168.25	✓
CC5965	453 #	Gel	135.90	✓
CC6077	735 #	Kalseal	367.50	✓
CC6079	147 #	Phenoseal	198.45	✓
CP8176	1	2 1/2" rubber plug	45.00	✓
		materials	2915.10	
		-30%	874.53	
		Subtotal		2040.57
SCANNED				
		6.5%	SALES TAX	132.64
			ESTIMATED TOTAL	4310.50

AUTHORIZATION [Signature] TITLE _____ DATE (6157.83)

acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's