



**THE BUIE CO., INC.**

P. O. Box 835  
 Wichita, KS 67201-0835  
 (316) 264-5105

INVOICE & TICKET

**No 2243**

WELL NO. AND FARM <b>Unruh "B" #1</b>	COUNTY <b>King</b>	STATE <b>KS.</b>	DATE <b>11-18-84</b>
CHARGE TO <b>Vincent Oil Corp</b>	WELL LOCATION <b>SEC. 26 TWP. 29 RANGE 19W</b>	CONTRACTOR <b>Wheatsfates Rig #1</b>	
	DELIVERED TO <b>Location</b>	LOCATION <b>1 Pratt</b>	CODE
	SHIPPED VIA <b>Co Vehicle</b>	LOCATION <b>2</b>	CODE
<b>275 SX A 30% CaCl<sub>2</sub></b>	TYPE AND PURPOSE OF JOB <b>Cement 8 5/8 Surface 527'</b>	LOCATION <b>3</b>	CODE
		WELL TYPE <b>New</b>	CODE

PRICE REFERENCE	DESCRIPTION	UNITS		UNIT PRICE	AMOUNT	
		QTY.	MEAS.			
4230-02	Pump Truck Charge	527	ft.	375/.40	465	80
4237-01	" " Mileage	42	mi.	2.10	88	20
4242-01	Class A Cement	275	Sx	5.00	1375	00
4245-01	Calcium chloride	7.75	cwt	22.50	174	38
4347-05	8 5/8 Top Wooden Plug	1	ea	50.00	50	00
4370-03	" Centralizer	52.1	ea	52.00	52	00
4374-03	" Aluminum Baffle Plate	1	ea	49.00	49	00
4240-01	Service Charge	288	ft <sup>3</sup>	.92	264	96
4448-01	Delivery 26625	Total Weight 42	Loaded Miles	558.6	Ton Miles .75	418 95

TERMS: DUE 30 DAYS FROM DATE OF INVOICE. TAX REFERENCES *Field est. only* SUB TOTAL **2,938.28**

IMPORTANT: SEE OTHER SIDE FOR TERMS AND CONDITIONS I HAVE READ, UNDERSTOOD AND AGREED TO THE TERMS AND CONDITIONS PRINTED ON THE REVERSE SIDE HEREOF AND REPRESENT THAT I HAVE FULL AUTHORITY TO ACCEPT SAME AND SIGN THIS ORDER.

TAX \_\_\_\_\_ TAX \_\_\_\_\_ TOTAL \$ **2,938.28**

*Dennis Pelt*  
 Customer or His Agent

*Dr. Duggitt*  
 The Buie Co., Inc. Operator

*Thank You*

SUBJECT TO CORRECTION





- Rotary Drilling
- Drilling Mud and Chemicals
- Heavy Oil Field Hauling
- Roustabout and Dirt Services
- Well Completion and Servicing Units

## Oilfield Services, Inc.

### DRILLER'S WELL LOG

Unruh "B" #1  
 C NE NW NE Sec. 26-29S-19W  
 Kiowa County, Kansas  
 Commenced: 11-16-84  
 Completed: 12-1-84  
 API #15-097-21,078  
 Operator: Vincent Oil Corporation

Depth		Formation	Remarks
From	To		
0	370	Sand, Red Bed	Ran 12 joints (511') new, 23#, 8 5/8" surface casing. Set at 521' with 275 sxs Class A, 3% cc. Job by Buie, ticket #2243. Cement did circulate. Plug down at 5:15 a.m.
370	1105	Red Bed	
1105	1350	Red Bed, Shale	
1350	2650	Shale	
2650	5117	Lime, Shale	
5117	5172	Mississippi	

RTD 5172'

Ran 124 joints, 4 1/2", 10 1/2# production casing. Set at 5171' with 75 sxs RFC, 500 gallons chemical wash and 2% KCL pre-flush. Job by Dowell, ticket #0306-4767. Plug down at 3:30 a.m. on December 1, 1984.

STATE OF KANSAS )  
 ) ss  
 COUNTY OF PRATT )

I, the undersigned, being duly sworn on oath, state that the above Driller's Log is true and correct to the best of my knowledge and belief and according to the records of this office.

WHEATSTATE OILFIELD SERVICES, INC.

  
 ARNIE LITTLE, VICE-PRESIDENT



  
 NOTARY PUBLIC

My Commission Expires:

3/22/88