



Services, Inc.

CHARGE TO: Dawson Nelson
 ADDRESS
 CITY, STATE, ZIP CODE

TICKET 27476

CITY, STATE, ZIP CODE

PAGE 1 OF 1

SERVICE LOCATIONS
 1. Hays, KS WELLS/PROJECT NO. 1-17 LEASE Thompson-Muckolls COUNTY/PARISH Pawnee STATE KS DATE 02/10/19 OWNER
 2. Ness City, KS TICKET TYPE DISCOVERY CONTRACTOR Discovery Drilling RIG NAME NO. Rig 2 SHIPPED VIA CT DELIVERED TO Location ORDER NO.
 3. WELLS TYPE Oil WELLS CATEGORY Development JOB PURPOSE Cement Deep Surface WELLS PERMIT NO. WELL LOCATION
 4. REFERRAL LOCATION INVOICE INSTRUCTIONS

PRICE REFERENCE	SECONDARY REFERENCE/ PART NUMBER	LOC	ACCT	DF	DESCRIPTION	QTY.			UNIT PRICE	AMOUNT
						QTY.	UM	QTY.		
575		1			MILEAGE #113	35	mi	1 EA	5.00	175.00
576D		1			Pump Charge - Deep Surface	1	EA	1 EA	1300.00	1300.00
296		1			D-Air	4	gal	1 EA	42.00	168.00
221		1			Liquid-KCL	2	gal	1 EA	25.00	50.00
412		1			Baffle Plate 8 5/8"	1	EA	1 EA	125.00	125.00
330		2			Swift Multi-Density Standard	375	SKS	1 EA	16.25	6093.75
276		2			Fleck	100	lbs	1 EA	2.50	250.00
581		2			Service Charge Cement	375	SKS	1 EA	1.25	468.75
583		2			Drayage	653.07	TM	35 mi	0.85	555.11

LEGAL TERMS: Customer hereby acknowledges and agrees to the terms and conditions on the reverse side hereof which include, but are not limited to, PAYMENT, RELEASE, INDEMNITY, and LIMITED WARRANTY provisions.

MUST BE SIGNED BY CUSTOMER OR CUSTOMER'S AGENT PRIOR TO START OF WORK OR DELIVERY OF GOODS

DATE SIGNED [Signature] TIME SIGNED A.M. P.M.

REMIT PAYMENT TO:
 SWIFT SERVICES, INC.
 P.O. BOX 466
 NESS CITY, KS 67560
 785-798-2300

SURVEY
 OUR EQUIPMENT PERFORMED WITHOUT BREAKDOWN?
 WE UNDERSTOOD AND MET YOUR NEEDS?
 OUR SERVICE WAS PERFORMED WITHOUT DELAY?
 WE OPERATED THE EQUIPMENT AND PERFORMED JOB CALCULATIONS SATISFACTORILY?
 ARE YOU SATISFIED WITH OUR SERVICE?
 CUSTOMER DID NOT WISH TO RESPOND

PAGE TOTAL 10910
 PAWNEE
 8435 80
 509 11
 TOTAL 8943 51

CUSTOMER ACCEPTANCE OF MATERIALS AND SERVICES: The customer hereby acknowledges receipt of the materials and services listed on this ticket.

SWIFT OPERATOR [Signature] APPROVAL [Signature]

Thank You!

SWIFT Services, Inc.

DATE: 02/16/19
TICKET NO.: 27476
PAGE NO.: 1

JOB LOG

CUSTOMER: *Downing & Nelson*

WELL NO.: *1-17*

LEASE: *Thompson-Nuckolls* JOB TYPE: *Deep Surface*

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	0001							On location, Rig Running Casing.
								RTD - 1230'
								29 Jts of 8 5/8" x 23#
								1230' Total Pipe set at 1230'
								Shoe Jt - 33.82'
								Baffle @ 1196'
	0115							Break Circulation.
	0145							Hook up to Swift
		4					400	Start water ahead
	0200	4	20				400	Fin water, Start SMD Cmt @ 11.8ppg
		4	59				400	Increase wt to 12.7ppg
		4	114				300	Increase wt to 13.5ppg
		4	129 1/2					Increase wt to 14.5ppg
	0230		143					Fin Cmt, Shut Down
							Vac	Release Plug, Start Displacement
							500	Catch Pressure
	0245						800	Land Plug, Cmt Circulated to Surface.
								Shut in
								Release Truck
								Washup
	0300							Rock up
	0310							Job Complete

Thanks
Jon, Austin, Russell