



PRESSURE PUMPING LLC

PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

12133
12010

TICKET NUMBER 55936
LOCATION Oakley, KS
FOREMAN Miles Staw

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice #814688

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
12-5-18	3613	Lillie 5	32	16 S	25 W	Wess
CUSTOMER			TRUCK #	DRIVER	TRUCK #	DRIVER
Hartman Oil			753	Corey W		
MAILING ADDRESS			5301T-129	Kevin Browning		
10500 E. Burkley Square Pkwy, Ste. 100			70	Kevin Browning		
CITY	STATE	ZIP CODE				
Wichita	KS	67206				

JOB TYPE 2 Stage HOLE SIZE 7 7/8" HOLE DEPTH 4622' CASING SIZE & WEIGHT 5.5" 15.5#
 CASING DEPTH 4621 DRILL PIPE _____ TUBING _____ OTHER DJ @ 1950'
 SLURRY WEIGHT 14.2/16.4 SLURRY VOL 1.4/1.9 WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 109' DISPLACEMENT PSI/SEC _____ MIX PSI _____ RATE _____

REMARKS: Safety meetings and Rig up on Hdr drilling #4 Run in casing 112 Sats Centralizer on Sats # 1, 3, 5, 6, 7, 8, 9, 10, 11, 12, 13, 14, 15, 16, 17, 18, 19, 20, 21, 22, 23, 24, 25, 26, 27, 28, 29, 30, 31, 32, 33, 34, 35, 36, 37, 38, 39, 40, 41, 42, 43, 44, 45, 46, 47, 48, 49, 50, 51, 52, 53, 54, 55, 56, 57, 58, 59, 60, 61, 62, 63, 64, 65, 66, 67, 68, 69, 70, 71, 72, 73, 74, 75, 76, 77, 78, 79, 80, 81, 82, 83, 84, 85, 86, 87, 88, 89, 90, 91, 92, 93, 94, 95, 96, 97, 98, 99, 100. Circulate casing thru Pump Mud flush and Water seal mix 100% Thix blend III w/ 5" Collo/Plat Shut down Clear Pump & lines Release plug displace 60 bls water and 49 bls mud with 850 psi lift Plus displace & hold @ 1500 psi. Prompt opening start open tool with 600 psi circulate casing thru Pump water Seal mix 400sv Lite-Weight blend III w/ 5" Disson down casing Shut down Clear Pump & lines Release plug displace 46.5 bls water with 850 psi lift Plus land & hold @ 1500 psi. Cement did Circulate

305x RH 205x MH Thru 1/2" Miles Staw

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0453	1	PUMP CHARGE	2800.00	2800.00
CE0007	30	MILEAGE	7.15	214.50
CE0710	24.05 Tons	Ton Mileage delivery	1.75	42.09
CE5831	450 SX	Lite-Weight Blend III	17.50	7875.00
CE5862	100 SX	Thix blend III	26.00	2600.00
CE6075	113 #	Collo Plate / Plat Seal	3.00	339.00
CE6077	500 #	Kol Seal	.50	250.00
CE6125	500 gal	Mud Flush	.65	325.00
CP8254	1	5/8" Latchdown Plug assembly	400.00	400.00
CP8485	1	5/8" Float Shoe AFU	585.00	585.00
CP8554	7	5/8" Centralizer	81	567.00
CP8629	1	5/8" Basket	385.00	385.00
CP8801	1	5/8" DU tool	5970.00	5970.00
			Subtotal	23573.12
			less 258d discount	5893.28
			Subtotal	17679.84
			SALES TAX	940.108
			ESTIMATED TOTAL	18620.53

AVIN 3737
 AUTHORIZATION [Signature] TITLE _____ DATE 12-5-18

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.