

# SWIFT Services, Inc.

DATE  
2-9-19

PAGE NO.

WELL NO. <i>1-31</i>		LEASE <i>Ruder</i>		JOB TYPE <i>Long String</i>		TICKET NO. <i>27460</i>		
START NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	300							On location
								5 1/2 x 14 # RTD - 3711 Set @ 3705 Shoe - 42.43 @ 3662.58 Centralizers - 1, 3, 5, 7, 9, 11
	430							Start Running Csg
	630							Break Circ on Bottom
	730	2	8			0		Plug Rat hole - 30 sks
	740	2	4			0		Plug Mouse Hole - 15 sks
	755					1800		Set Packer Shoe
	800	5	12			400		Pump Mud flush - 500 gal
	805	5	20			400		Pump Kal spacer
	810	5	32			400		pump CRT - 130 sks @ 15.5 rpm
	825							Drop plug. Wash PC
	830	6.5	0			200		Start Disp
	845	6	89			1000/1700		Land Plug - lift psi - 1000 # <del>can</del> land psi - 1700 #
						1800		Release Psi - Flowing Back Repressure Release psi - Dry
								Job Complete
								Thanks David, Zech & Kirby