

*m*

# SWIFT Services, Inc.

DATE 2-23-19 PAGE NO. 3

## JOB LOG

CUSTOMER Downing - Nelson WELL NO. 1-17 LEASE THOMPSON - Nickolls JOB TYPE Long String TICKET NO. 27469

CHART NO.	TIME	RATE (BPM)	VOLUME (BBL) (GAL)	PUMPS		PRESSURE (PSI)		DESCRIPTION OF OPERATION AND MATERIALS
				T	C	TUBING	CASING	
	1130							on location
								14 # x 5 1/2 RTD - 4456 TOTAL Pipe - 4452 SHOE - 42.42 Baffle @ 4409 CENTRALIZERS - 1, 3, 5, 7, 9, 11
	1630							START Running Csg
	1830							Circ on Bottom
	1900	2	8			0		Plug rat hole - 30 sks
	1905	5	12			300		pump Mudflush - 500 GAL
		5	20			300		pump Kcl spacer
	1915	5.25	42			300		Pump Cmt - 170 sks @ 15.5 <sup>PPG</sup>
								Drop plug - Wash P&L
	1930	6	0			300		Start Disp
	2000	2	107.5			900/1500		LAND Plug - lift - 950 # land - 1500 #
								Release Psi - Dry
								Job Complete
								Thanks David, Zach, & Kirby