

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. 4342
 Foreman David Gardner
 Camp Eureka

API # 15-207-21648-00-02

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
3-6-19	1000	Klick #38	20	25 S	14 E	Woodson	KS
Customer			Unit #	Driver		Unit #	Driver
Trimble & MacLasky Oil, LLC			105	Jason H.			
Mailing Address			110	Russell M.			
P.O. Box 171			141	Allen B.			
City	State	Zip Code					
Gridley	KS	66852					

Job Type P.T.A. Old well Hole Depth 1450' G.L. Slurry Vol. 14.5 Bbl Tubing 2 7/8" @ 1375'
 Casing Depth 1445' Hole Size _____ Slurry Wt. 14# Drill Pipe _____
 Casing Size & Wt. 4 1/2" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 2 7/8" tubing. Establish injection rate w/ 4 Bbl fresh water @ 3.5 BPM @ 250 PSI. Mixed 65 sks 60/40 Pozmix Cement w/ 4% Gel @ 14# / gal, yield 1.25 = 14.5 Bbl Slurry. Final mixing PSI of 350 PSI. Shut down. Held 150 PSI. Shut well in. Job complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	785.00	785.00
C107	20	Mileage	4.20	84.00
C203	65 sks	60/40 Pozmix Cement	13.40	871.00
C206	225#	Gel @ 4%	.21	47.25
C214	45#	Cottonseed Hulls - Mixed in w/Cement	.50	22.50
C108A	2.795 Tons	Ton Mileage - Bulk Truck	m/c	365.00
C113	2 HRS	80 Bbl Vac Truck	90.00 /HR	180.00
C224	2500 Gals	City Water	10.00 / 1000 Gal	25.00
<i>Thank You</i>				
			Sub Total	2,379.75
			Less 5%	127.91
			Sales Tax	178.48
			7.5%	
Authorization _____ Title _____			Total	2,430.32

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.