

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4217**
 Foreman David Gardner
 Camp Eureka

| Date | Cust ID # | Lease & Well Number | Section | Township | Range | County | State |
|---------------------------------|-----------|---------------------|---------|----------|----------|----------|--------|
| 11-2-18 | 1003 | JCB Miller #35 | | | | Anderson | KS |
| Customer Colt Energy Inc. | | | Unit # | | Driver | Unit # | Driver |
| Mailing Address P.O. Box 288 | | | 105 | | Jason H. | | |
| City Toka | | | 110 | | Steve M. | | |
| State KS | | Zip Code 666749 | | | | | |

Job Type Longstring Hole Depth 1000' Slurry Vol. 35 Bbl Tubing _____
 Casing Depth 986.70' Hole Size 6 3/4" Slurry Wt. 13.8" Drill Pipe _____
 Casing Size & Wt. 4 1/2" 11.60" Cement Left in Casing 4' 55" Water Gal/SK _____ Other _____
 Displacement 15 1/2 Bbl Displacement PSI 500 Bump Plug to 900 BPM _____

Remarks: Safety Meeting. Rig up to 4 1/2 casing. Break circulation w/ fresh water. Mixed 300' Gel flush w/ Hulls. Pump 5 Bbl fresh water spacer. Mixed 115 SKS Thick Set Cement w/ 2" Phenoxal/sk @ 13.8"/gal, yield 1.68 = 35 Bbl Slurry. Shut down. Wash out pump + lines. Release 4 1/2 Top Rubber Plug. Displace w/ 15.5 Bbl fresh water. Final pumping pressure of 500 PSI. Pump plug to 900 PSI wait 2 mins. Release pressure. Float + Plug held. Good circulation @ all times while cementing. Good cement returns to surface = 5 Bbl good cement slurry to pit. Job complete. Rig down.

| Code | Qty or Units | Description of Product or Services | Unit Price | Total |
|------------------|--------------|------------------------------------|------------|-------|
| C102 | 1 | Pump Charge | | |
| C107 | 45 | Mileage | | |
| C201 | 115 SKS | Thick Set Cement | | |
| C208 | 230" | Phenoxal @ 2"/sk | | |
| C109B | 16.325 Ton | Ten Mileage | | |
| C206 | 300" | Gel Flush | | |
| C214 | 45" | Cottonseed Hulls | | |
| 403 | 1 | 4 1/2 Top Rubber Plug | | |
| <u>Thank You</u> | | | | |
| | | | Sub Total | |
| | | | Less 5% | |
| | | | Sales Tax | |
| | | | 8.0% | |
| | | | Total | |

Authorization _____ Title _____

I agree to the payment terms and conditions of services...