

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4213**
 Foreman David Gardner
 Camp Eureka

NPI# 15-003-261032

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
10-30-18	1003	Martin #12	29	22 S.	19 E.	Anderson	KS
Customer			Unit #	Driver	Unit #	Driver	
Calt Energy Inc.			105	Jason H.			
Mailing Address			110	Zevi A.			
P.O. Box 388							
City	State	Zip Code					
Toola	KS	666749					

Job Type Longstring Hole Depth 1000' Slurry Vol. 25 Bbl Tubing _____
 Casing Depth 977.55' Hole Size 6 3/4" Slurry Wt. 13.8# Drill Pipe _____
 Casing Size & Wt. 4 1/2 16.6# Cement Left in Casing 4' 55" Water Gal/SK _____ Other _____
 Displacement 16 Bbl Displacement PSI 550 Bump Plug to 950 BPM _____

Remarks: Safety meeting Rig up to 4 1/2 casing. Break circulation w/ fresh water. Mixed 300' Gel Flush w/ Hulls. 5 Bbl fresh water spacer. Mixed 115 ses Thick Set Cement w/ 2" Pheno seal/sk @ 13.8#/gal, yield 1.68 = 35 Bbl slurry. Shut down wash out pump 4 lines. Release 4 1/2 Top Rubber Plug Displace w/ 16 Bbl fresh water. Good circulation @ all times. Good cement returns to surface = 5 Bbl good cement slurry to pit. Wait 2 mins. Release pressure. Float 4 plug held. Final pumping pressure of 550 PSI. Pump plug to 950 PSI. Job complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge		
C107	45	Mileage		
C201	115 ses	Thick Set Cement		
C208	220#	Pheno seal @ 2"/sk		
C108B	6.325 Tons	Tan Mileage		
C206	300#	Gel Flush		
C214	45"	Hulls		
C403	1	4 1/2 Top Rubber Plug		
<u>Thank You</u>				
			Sub Total	
			Less 5%	
Authorization <u>R.R. [Signature]</u> Title _____			Sales Tax	
			Total	

I agree to the payment terms and conditions of services provided by the Elite Cementing & Acid Service, LLC.