

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4222**
 Foreman David Gardner
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
11-15-18	1002	Martin # I15				Anderson	KS
Customer Cott Energy, Inc.			Safety Meeting DG SH CG	Unit # 105 112	Driver Jason H. Caleb G.	Unit #	Driver
Mailing Address P.O. Box 388							
City Iola		State KS	Zip Code 66749				

Job Type Logging Hole Depth 1000' Slurry Vol. 35 Bbl Tubing _____
 Casing Depth 981.65' Hole Size 10 3/4" Slurry Wt. 13.8" Drill Pipe _____
 Casing Size & Wt. 4 1/2" 11.60# Cement Left in Casing 4' 5" Water Gal/SK 90 Other _____
 Displacement 16 Bbl Displacement PSI 500 Bump Plug to 900 BPM _____

Remarks: Safety Meeting. Rig up to 4 1/2 casing. Break circulation w/ fresh water. Mixed 300# Gel flush w/ hulls. Pump 5 Bbl fresh water spacer. Mixed 115 sks Thick Set Cement w/ 2" Phenoxal /SK @ 13.8"/gal, yield 1.68 = 35 Bbl slurry. Wash out pump & lines. Shut down. Release 4 1/2 top Rubber plug. Displace w/ 16 Bbl fresh water. Final pumping pressure of 500 PSI. Bump plug to 900 PSI. Wait 2 mins. Release pressure. Float + Plug held. Good circulation @ all times while cementing to Bbl good cement slurry to pit. Job complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C102	1	Pump Charge		
C107	45	Mileage		
C201	115 sks	Thick Set Cement		
C205	230#	Phenoxal @ 2"/sk		
C108B	6.325 Tons	Ten Mileage		
C206	300#	Gel Flush		
C214	45#	Cottonseed Hulls		
C403	1	4 1/2 Top Rubber Plug		
<u>Thank You</u>				
			Sub Total	
			Less 5%	
			8.0%	
			Sales Tax	
Authorization _____	Title _____			Total

I agree to the payment terms and conditions of service provided on the back of this report.