

D.S. & W. Well Servicing, Inc.

1822 24th Street
Great Bend, KS 67530

Invoice

Date	Invoice #
3/1/2019	73320

Bill To
Richlan Drilling 598 2nd Ave. Beaver, KS 67525

Lease Name	Terms	Due Date
Beran #1 - Plug	30 Days	3/31/2019

Item	Description	Qty	Rate	Amount
Rig #17	Cardwell KB 150 Double Drum Pole - #17	8.5	205.00	1,742.50T
Workover Head	Workover Head	1	100.00	100.00T
Stripper Rubber	2-3/8" Stripper Rubber - Used	0.5	152.00	76.00T
Solvent	Cleaning Solvent	2	7.00	14.00T
Thread Dope	Thread Dope	1	17.50	17.50T

Thank You

Subtotal \$1,950.00

Sales Tax (7.5%) \$146.25

Total \$2,096.25

620-793-5838 Office
620-793-5860 Fax



Balance Due \$2,096.25

Pd 3-15-19
CHK 10207

D.S.&W. WELL SERVICING, INC.

1822 24th Street
Great Bend, KS 67530

Date: 03/01/19

Lease: Beran

Company: Richlan Drilling

Well: #1 - Plug

Address: 598 2nd Ave., Beaver, KS 67525

Invoice #: 73320

WELL PULLING REPORT

PULLED			EQUIPMENT	RUN		
JTS.	FT.	DESCRIPTION		JTS.	FT.	DESCRIPTION
			MUD ANCHOR			
			ANCHOR CATCHER			
			SEATING NIPPLE			
			WORKING BARREL			
			TUBING			
			TUBING SUBS			
			STRAINER GAS ANCHOR			
			TRAVELING VALVE			
			PUMP			
			RODS			
			RODS			
			ROD SUBS			
			POLISH ROD			
			LINER			

Cardwell KB 150 Double Drum Pole Rig #17, operator & crew of 2 men	8.5 hrs @	\$ 205.00	\$	1,742.50
Materials & Equipment Used: <u>Workover Head</u>			\$	100.00
<u>2-3/8" Stripper Rubber - Used - .5 @ \$152</u>			\$	76.00
<u>Solvent - 2 gallons @ \$7.00</u>			\$	14.00
<u>Thread Dope - 1 trip @ \$17.50</u>			\$	17.50
Sub-Total			\$	1,950.00
Sales Tax - Barton County 7.5% - Plug			\$	146.25
Total Due			\$	2,096.25

03/01/19 - 8.5 Rig hrs - Drove to location. Held tailgate safety meeting. Move in and rig up. Rig up perforators. Perforate @ 1400', 715' and 350'. Run tubing in to 3200'. Set 1st plug: 50 sacks cement, 11 sacks gel and 200# hulls. Pull 55 jts. Set 2nd plug: 70 sacks cement, 110# hulls. Pull 23 jts. Set 3rd plug: 100 sacks cement. Circulated. Pull remainder of the tubing, 22jts. Top off to surface with 125 sacks cement. Circulate. Clean tools. Rig down and move off.

Date Work
Commenced 03/01/19

Date Work
Completed 03/01/19

D.S.&W. WELL SERVICING, INC.

By Alex Hernandez

D.S. & W. Well Servicing, Inc.

Telephone (620) 793-5838 - 1822 24th Street - Great Bend, KS 67530

**DAILY
WORKOVER
REPORT**

Company Richlan Drilling Date 03/01/19
 Rig# 17 Lease Beran Well# 1 City _____
 Section _____ Township _____ Range _____ County BT State Ks

Qty	Special Tools / Supplies Used	Date:	Operator:	HRS.
1	Workover head	<u>3/1/19</u>	<u>Alex H.</u>	<u>8 1/2</u> ✓
1	2 3/8" used stripping rubber		<u>Alonzo A.</u>	<u>8 1/2</u> ✓
2	gal solvent		<u>Carlos A.</u>	<u>8 1/2</u> ✓
1	Trip thread dope			

Work Performed: MIRU TBSM
Dig up perforators, perforate at 1400', 715', and 350'.

Run tubing into 3200' set 1st plug = 11 sacks gel, 50 sacks cement, 200 lbs hulls
Pull 55 joints, set 2nd plug = 70 cement sacks, 110 lbs of hulls
Pull 23 joints, set 3rd plug = 100 sacks cement, gel circulated. Pull rest of the tubing (22 joints) top off to surface 125 cement to circulate.

Qty	Special Tools / Supplies Used	Date:	Operator:	HRS.

Work Performed: Clean tools, rig down, move off.

Qty	Special Tools / Supplies Used	Date:	Operator:	HRS.

Work Performed: _____