



PRESSURE PUMPING LLC
PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

TICKET NUMBER **55518**

LOCATION Ottawa, KS

FOREMAN Casey Kennedy

**FIELD TICKET & TREATMENT REPORT
CEMENT**

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10/30/18	4015	Hays # P-8	NW29	17	22	M
CUSTOMER JTC Oil Inc.			TRUCK #	DRIVER	TRUCK #	DRIVER
MAILING ADDRESS 35790 Plum Creek Rd			729	Casey Ken	✓ Safety Meeting	
CITY Osawatimie			495	KeiCar	✓	
STATE KS			503	KeiDet	✓	
ZIP CODE 66064			369	HarBec	✓	

JOB TYPE long string HOLE SIZE 5 7/8" HOLE DEPTH 620' CASING SIZE & WEIGHT 2 7/8" EVE
 CASING DEPTH 604' DRILL PIPE _____ TUBING _____ OTHER _____
 SLURRY WEIGHT _____ SLURRY VOL _____ WATER gal/sk _____ CEMENT LEFT in CASING _____
 DISPLACEMENT 3.50 bbls DISPLACEMENT PSI _____ MIX PSI _____ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 200 # Gel followed by 5 bbls fresh water, mixed & pumped 60 sks Thixblend II cement w/ 1# Pheno seal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w/ 3.50 bbls fresh water, pressured to 800 PSI, released pressure to set float valve.

Handwritten signature

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	
CE0002	20 mi	MILEAGE	143.00	
CE0711	1/2 min	ten mileage	330.00	
WE0853	1.5 hrs	80 Vac	150.00	
		trucks	2123.00	
		- 45%	955.35	
		Subtotal		1167.65
CC5861	60 sks	Thixblend II cement	1620.00	
CC6079	60 #	Pheno seal	81.00	
CC5965	200 #	Gel	60.00	
CP8176	1	2 1/2" rubber plug	45.00	
		materials	1806.00	
		- 45%	812.70	
		Subtotal		993.30
		8%		79.46
		SALES TAX		79.46
		ESTIMATED TOTAL		2240.41

SCANNED

RAVIN 3737
 AUTHORIZATION No Co Rep TITLE _____ DATE (4073.48)
 Tom Cain by phone

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.