



PRESSURE PUMPING LLC  
 PO Box 884, Chanute, KS 66720  
 620-431-9210 or 800-467-8676

**FIELD TICKET & TREATMENT REPORT**  
**CEMENT**

TICKET NUMBER **55519**  
 LOCATION Ottawa, KS  
 FOREMAN Casey Kennedy

DATE	CUSTOMER #	WELL NAME & NUMBER	SECTION	TOWNSHIP	RANGE	COUNTY
10/30/18	4015	Hays # I-2	NW 29	17	22	M1
CUSTOMER JTC Oil Inc.						
MAILING ADDRESS 35790 Plum Creek Rd						
CITY Osawatomie		STATE KS	ZIP CODE 66004			

TRUCK #	DRIVER	TRUCK #	DRIVER
729	Gas Ken	✓ Safety Meeting	
495	Kei Car	✓	
503	Kei Det	✓	
369	Har Bec	✓	

JOB TYPE longstring HOLE SIZE 5 7/8" HOLE DEPTH 400' CASING SIZE & WEIGHT 2 7/8" EUE  
 CASING DEPTH 577' DRILL PIPE \_\_\_\_\_ TUBING \_\_\_\_\_ OTHER \_\_\_\_\_  
 SLURRY WEIGHT \_\_\_\_\_ SLURRY VOL \_\_\_\_\_ WATER gal/sk \_\_\_\_\_ CEMENT LEFT in CASING \_\_\_\_\_  
 DISPLACEMENT 3.34 bbls DISPLACEMENT PSI \_\_\_\_\_ MIX PSI \_\_\_\_\_ RATE 4 bpm

REMARKS: held safety meeting, established circulation, mixed & pumped 200 # Gel followed by 5 bbls fresh water, mixed & pumped 100 sks Thixoblend II cement w/ 1# Phenoseal per sk, cement to surface, flushed pump clean, pumped 2 1/2" rubber plug to casing TD w 3.34 bbls fresh water, pressured to 800 PSI, well held pressure for 30 min MIT, released pressure to set float valve.

*[Handwritten signature]*

ACCOUNT CODE	QUANTITY or UNITS	DESCRIPTION of SERVICES or PRODUCT	UNIT PRICE	TOTAL
CE0450	1	PUMP CHARGE	1500.00	
CE0002	—	MILEAGE	—	
CE0711	1/2 min	low mileage	330.00	
WE0853	1.5 hrs	80 vac	150.00	
		trucks	1980.00	
		- 45%	891.00	
		Subtotal		1089.00
CC5861	60 sks	Thixoblend II cement	1620.00	
CC10079	60 #	Phenoseal	81.00	
CC5965	200 #	Gel	60.00	
CP8176	1	2 1/2" rubber plug	45.00	
		materials	1806.00	
		- 45%	812.70	
		Subtotal		993.30
		8%		79.46
		SALES TAX		79.46
		ESTIMATED TOTAL		2161.76

**SCANNED**

AUTHORIZATION No rep on site TITLE \_\_\_\_\_ DATE \_\_\_\_\_  
 Tom Cain by phone  
 ESTIMATED TOTAL 2161.76  
 (3930.48)

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.