

D. D. Sandlin Drilling Co.

Rotary Drilling -- Diamond Coring

DRILLED FOR: LARRY MOORE ^{Iola, Kansas 66749} RANCH INC.
 % JOE PHILLIPS
 GRIDLEY, KANSAS
 FARM LAWRENCE
 WELL # 11
 COFFEY COUNTY, KANSAS

THICKNESS	FORMATIONS	TOTAL DEPTH
2	soil	2
13	clay	15
6	sand stone w/ clay	21
41	shale	62
5	lime	67
4	shale	71
5	lime	76
140	shale	216
38	shale w/ lime st	254
49	lime	303
15	shale	318
34	lime	352
24	shale sandy	376
110	lime	486
39	shalley white lime	525
6	lime	531
47	shale	578
1 14	lime	692
146	shale	836
24	shale w/ lime st	860
29	lime w/ shale st	889
3	shale black	892
7	lime	899
29	sandy shale	928
28	sand	956
29	lime	985
5	shale black	990
36	lime	1026
5	shale black	1031
2	lime	1033
10	shale w/ lime st	1043
17	oil sand broken	1060
26	shale	1086

T.D.

set 60' of 7" surface pipe an cemented
 cored from 1044' to 1064'
 set 1083' of 4" pipe with float on
 bottom, cemented to surface.
 used 4" pipe.