

John Roy Evans Oil Company, LLC
Penka Lease Well# 26-1
15-009-26231-00-00
Barton County, KS
Sec 26 T17S R12W

<u>DST #1</u>	3161-3195
	30-30-45-60
1 st Open	BOB 5 min.
1 st Close	Built to ¾"
2 nd Open	BOB 30 sec.
2 nd Close	Built to 1 ½"
Recovered	1275' GIP
	50' HOCM (30% oil, 7% mud)
	63' HOCM (40% oil, 60% mud)
ISIP	863 psi
FSIP	894 psi
IFP	12-34 psi
FFP	38-59 psi
HSH	1441-1434 psi
<u>DST#2</u>	3198-3250
	30-30-45-60
1 st Open	BOB 4 min.
1 st Close	Built to 12"
2 nd Open	BOB 1.5 min.
2 nd Close	BOB 20.5 min.
Recovered	972' GIP
	855' SLGCMO (10% gas, 38% oil, 52% mud)
ISIP	996 psi
FSIP	993 psi
IFP	25-173 psi
FFP	201-326 psi
HSH	1488-1474 psi
<u>DST#3</u>	3260-3334
	30-20-15
1 st Open	Weak surface blow
1 st Close	No BB
2 nd Open	Dead
Recovered	10' clean oil, 10' SLMCO (95% oil, 5% mud)
	63' HOCM (30% oil, 70% mud)
ISIP	981 psi
FSIP	0 psi
IFP	11-31 psi
FFP	33-42 psi
HSH	1531-1525 psi
<u>DST#4</u>	3260-3240
	30-30-30-30
1 st Open	Fair blow. 10"@30 min.
1 st Close	Built to ¼"
2 nd Open	Fair blow. 7"@30 min.
2 nd Close	Built to WSB
Recovered	32' clean oil, 30' SLOCM (15% oil, 85% mud)
	63' SLOCM (5% oil, 95% mud)
ISIP	1035 psi
FSIP	966 psi
IFP	15-39 psi
FFP	41-61 psi
HSH	1512-1512 psi