

10 E 7TH
 O Box 92
 Eureka, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4349**
 Foreman David Gardner
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
3-20-19	1021	Bays #3				Greenwood	KS	
Customer <u>C? Oil</u>			Unit #		Driver		Unit #	Driver
Mailing Address <u>600 Arrowhead Dr.</u>			105		Jason H.			
			119		Zevi A.			
			145		Steve M.			
City <u>New Strawn</u>		State <u>KS</u>	Zip Code <u>66839</u>					

Job Type P.T.A. Old well Hole Depth 11092' Slurry Vol. 20 Bbl Tubing _____
 Casing Depth _____ Hole Size _____ Slurry Wt. 14" Drill Pipe _____
 Casing Size & Wt. 3" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety meeting. Rig up to 3" casing. Establish injection rate of 2.7 BPM @ 1000 PSI. Mixed 75 SKS 100/40 Pozmix Cement w/ 4% Gel, 2% Caclz @ 14"/gal. yield 1.50 = 20 Bbl Slurry, w/ Hulls mixed in cement. Pressured up to 1000 PSI. Shutdown. Staged on cement for 1 Hour. Released pressure. No flow back. Well stayed full. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge 1 st of 2 wells	785.00	785.00
C107	30	Mileage	4.20	126.00
C203	75 SKS	100/40 Pozmix Cement	13.40	1005.00
C206	260 [#]	4% Gel	.21	54.60
C205	130 [#]	2% Caclz	.63	81.90
C214	45 [#]	Cotteseed Hulls	.50	22.50
C108A	3.225 Tons	Tea Mileage - Bulk Truck	m/c	365.00
C113	1.5 HRS	80 Bbl Vol C Truck	90.00 / HR	135.00
C224	3300 Gals	City Water	10.00 / 1000	33.00
<u>Thank You</u>				
			Sub Total	2608.00
			Less 5%	140.18
			Sales Tax	195.60
			7.5%	
Authorization by <u>Chris Harris</u> Title _____			Total	2663.42

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.