

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report
 Ticket No. **4411**
 Foreman David Ender
 Camp Eureka

Date	Cust. ID #	Lease & Well Number		Section	Township	Range	County	State
3-20-19	1021	Snyder #30					Greenwood	KS
Customer			Safety Meeting DG JH ZM SM	Unit #	Driver	Unit #	Driver	
Mailing Address				105	Jason H.			
1000 Arrowhead Dr.				114	Zevi A.			
City				145	Steve M.			
New Strawn		State	Zip Code					
		KS	66839					

Job Type P.T.A. Old well Hole Depth 1720' Slurry Vol. 20 Bbl Tubing _____
 Casing Depth _____ Hole Size _____ Slurry Wt. 14" Drill Pipe _____
 Casing Size & Wt. 3" Cement Left in Casing _____ Water Gal/SK _____ Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Rig up to 3" casing. Establish injection rate of 1 BPM @ 750 PSI. Mixed 75 SKS 100/40 Permox Cement w/ 4% Gel, 2% Gatz. @ 14"/gal, yield 1.50 = 20 Bbl Slurry, w/ Hulls mixed in cement. Pressured up to 1000 PSI. Shut down. Hold 200 PSI. Shut well in. Job complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105-2	1	Pump Charge 2 nd well	525.00	525.00
C107	N/C	Mileage within 3 miles of 1 st well	N/C	0
C203	75 SKS	100/40 Permox Cement	13.40	1005.00
C206	260 ^{lb}	Gel @ 4%	.21	54.60
C205	130 ^{lb}	Gatz @ 2%	.63	81.90
C214	45 ^{lb}	Cottonseed Hulls	.50	22.50
C113	1.5 HRS.	80 Bbl Vac Truck	90.00/HR	135.00
<u>Thank You</u>				
			Sub Total	1829.10
			Less 5%	98.04
			Sales Tax	136.80
Authorization by <u>Chris Haas</u> Title _____			Total	1862.76

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.