



RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

Brewer 8-A

			Start 12-21-18
			Finish 12-23-18
7	soil	7	
25	clay/gravel	32	
65	shale	97	
77	lime	174	
101	shale	275	
122	lime	397	
32	shale	429	
73	lime	502	Set 40' of 7" w/5sxs
4	shale	506	Ran 981' of 2 7/8
47	lime	553	cemented to surface 125sxs
189	shale	742	
26	lime	768	
44	shale	812	
34	lime	846	
15	shale	861	
7	lime	868	
16	shale	884	
2	lime	886	
12	shale	898	
3	lime	901	
40	shale	941	
2	Sandy shale	943	
9	bkn sand	952	good show
39	Shale	991	T.D.