

810 E 7<sup>TH</sup>  
 PO Box 92  
 EUREKA, KS 67045  
 (620) 583-5561



**Cement or Acid Field Report**  
 Ticket No. **4373**  
 Foreman Kevin McCoy  
 Camp EUREKA

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State	
3-19-19	1165	King # 3	29	33S	2E	SUMNER	Ks	
Customer <u>B5 Operating, LLC</u>			Safety Meeting KM AM CG		Unit #	Driver	Unit #	Driver
Mailing Address <u>P.O. Box 45</u>					104	ALAN M.		
City <u>Wellington</u>					113	CALEB G.		
State <u>Ks</u>		Zip Code <u>67152</u>						

Job Type P.T.A old well Hole Depth \_\_\_\_\_ Slurry Vol. 23.5 BBL Tubing \_\_\_\_\_  
 Casing Depth \_\_\_\_\_ Hole Size 7 7/8 Slurry Wt. 14.1 # Drill Pipe \_\_\_\_\_  
 Casing Size & Wt. 5 1/2 Cement Left in Casing \_\_\_\_\_ Water Gal/SK 6.7 Other \_\_\_\_\_  
 Displacement \_\_\_\_\_ Displacement PSI \_\_\_\_\_ Bump Plug to \_\_\_\_\_ BPM \_\_\_\_\_

Remarks: SAFETY Meeting: 5 1/2 PERFORATED @ 250'. Rig up to 5 1/2 casing. BREAK CIRCULATION w/ 5 BBL water w/ Good Fluid Returns to SURFACE ON ANNULUS OF 5 1/2. MIXED 95 SKS 60/40 Pozmix Cement w/ 4% GeL, 2% CaCl2 @ 14.1 #/gal = 23.5 BBL Slurry. Good Cement to SURFACE. Shut down. Shut in well w/ Cement @ SURFACE. Job Complete. Rig down.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C 105	1	Pump Charge	785.00	785.00
C 107	60	Mileage	4.20	252.00
C 203	95 SKS	60/40 Pozmix Cement	13.40	1273.00
C 206	325 #	GeL 4%	.21 #	68.25
C 205	165 #	CaCl2 2%	.63 #	103.95
C 108 A	4.09 TONS	TON Mileage	M/C	225.00
			Sub Total	2707.20
			Less 5%	145.51
			7.5% Sales Tax	203.04
Authorization <u>Witnessed By Mitch Bartelso</u> Title _____			Total	2764.73

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.