

Form	ACO1 - Well Completion
Operator	RJ Energy, LLC
Well Name	WEBB W 3-I
Doc ID	1459681

Casing

Purpose Of String	Size Hole Drilled	Size Casing Set	Weight	Setting Depth	Type Of Cement	Number of Sacks Used	Type and Percent Additives
Surface	9.875	7	17	42	portland	4	
Production	5.875	2.875	6.5	1004	portland	125	

HAMMERSON CORPORATION

PO BOX 189
Gas, KS 66742

Invoice

Date	Invoice #
1/27/2019	14194

Bill To
R.J. ENERGY LLC 22082 NE NEOSHO RD GARNETT, KS 66032

P.O. No.	Terms	Project
	Due on receipt	

Quantity	Description	Rate	Amount
125	WELL MUD (\$8.00 PER SACK) Well Brewer #1	8.00	1,000.00T
1.5	TRUCKING (\$50 PER HOUR)	50.00	75.00T
125	WELL MUD (\$8.00 PER SACK) Well Webb 31	8.00	1,000.00T
1	TRUCKING (\$50 PER HOUR)	50.00	50.00T
125	WELL MUD (\$8.00 PER SACK) Well Brewer 7A	8.00	1,000.00T
2	TRUCKING (\$50 PER HOUR)	50.00	100.00T
	SALES TAX	6.50%	209.63
Thank you for your business.		Total	\$3,434.63



Mound City, KS

620.224.7406

Well #					Casing			
Webb W #3-I RJ ENERGY, LLC					Surface		Longstring	
					Size:	7.0 "	Size:	2 7/8 "
					Tally:	42.8 '	Tally:	1004 '
					Cement:	4 sx	Bit:	5.875 "
API #:	15-031-24355	S-T-R:	11-23-16E		Bit:	9.875 "	Date:	1/24/2019
County:	Coffey	Date:	1/10/2019					
Top	Base	Formation		Top	Base	Formation		
0	2	Soil						
2	12	Clay						
12	25	Sand & gravel						
25	130	Shale						
130	135	Lime						
135	152	Sand	White					
152	198	Lime						
198	296	Shale						
296	310	Lime						
310	319	Shale						
319	427	Lime						
427	447	Shale						
447	458	Lime						
458	471	Shale						
471	476	Lime						
476	477	Shale						
477	529	Lime						
529	533	Shale						
533	584	Lime						
584	513	Shale						
749	777	Lime						
777	844	Shale						
844	849	Lime						
849	742	Shale						
870	878	Lime		Sand / Core Detail				
878	910	Shale		Core #1:		Core #2:		
910	916	Lime		959	962	Odor (slight), no bleed.		
916	958	Shale						
958	959	Lime		962	968	Good odor, fair bleed, slightly laminated, soft.		
959	974	Sand						
974		Sandy Shale		968	973	Good odor, good bleed, soft sand, slightly		
1008		TD				laminated.		
				973		Blk. Sand, slight odor.		