



PAGE 1 of 1	CUST NO 1004409	YARD # 1718	INVOICE DATE 04/03/2017
INVOICE NUMBER 92390152			

Pratt (620) 672-1201
 B VAL ENERGY
 I 125 n market ste 1710
 L WICHITA
 L KS US 67202
 T
 O ATTN: ACCOUNTS PAYABLE

J LEASE NAME GMX Kriss Unit 1-8
 O LOCATION
 B COUNTY Thomas
 S STATE KS
 I JOB DESCRIPTION Cement-New Well Casing/Pi
 T
 E JOB CONTACT

JOB #	EQUIPMENT #	PURCHASE ORDER NO.	TERMS	DUE DATE
41012873	19919		Net - 30 days	05/03/2017

	QTY	U of M	UNIT PRICE	INVOICE AMOUNT
<i>For Service Dates: 03/28/2017 to 03/28/2017</i>				
0041012873				
171814316L Cement-New Well Casing/Pi 03/28/2017 Cement Production Casing				
AA2 Cement	125.00	EA	7.99	998.75 T
A-Con' Blend	400.00	EA	8.46	3,384.00 T
60/40 POZ	30.00	EA	5.64	169.20 T
Celloflake	132.00	EA	1.74	229.68 T
C-41P	30.00	EA	1.88	56.40 T
Salt	492.00	EA	0.24	118.08 T
Mag Chem 10CR	352.00	EA	1.27	447.04 T
C-15	94.00	EA	5.88	552.72 T
Super Flush II	500.00	EA	0.72	360.00 T
Gilsonite	625.00	EA	0.31	193.75 T
Calcium Chloride	1,128.00	EA	0.49	552.72 T
"Two Stage Cement Collar, 5 1/2" (Blue)	1.00	EA	2,115.00	2,115.00
"Auto Fill Float Shoe 5 1/2" (Blue)"	1.00	EA	169.20	169.20
5 1/2 x 7 7/8 W/Fins(green)	7.00	EA	35.25	246.75
"5 1/2" Basket (Blue)"	1.00	EA	136.30	136.30
"Unit Mileage Chg (PU, cars one way)"	100.00	MI	2.12	212.00
Heavy Equipment Mileage	300.00	MI	3.53	1,059.00
"Proppant & Bulk Del. Chgs., per ton mil	2,596.00	EA	1.18	3,063.28
Blending & Mixing Service Charge	555.00	BAG	0.66	366.30
Plug Container Util. Chg.	1.00	EA	117.50	117.50
High Head Charge (Over 6')	1.00	EA	141.00	141.00
Depth Charge; 4001'-5000'	1.00	EA	1,184.40	1,184.40
"Service Supervisor, first 8 hrs on loc.	1.00	EA	82.25	82.25

PLEASE REMIT TO:	SEND OTHER CORRESPONDENCE TO:	SUB TOTAL	15,955.32
BASIC ENERGY SERVICES, LP	BASIC ENERGY SERVICES, LP	TAX	564.99
PO BOX 841903	801 CHERRY ST, STE 2100	INVOICE TOTAL	16,520.31
DALLAS, TX 75284-1903	FORT WORTH, TX 76102		



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Val Energy Inc.	Cement Pump No.:	37223, 19919 9Hrs.	Operator TRK No.:	78938
Address:	125 N. Market Ste 1710	Ticket #:	1718 14316 L	Bulk TRK No.:	70897, 19578 Santiago
City, State, Zip:	Wichita Ks 67206	Job Type:	Z42 - Cement Production Casing		
Service District:	1718 - Liberal, Ks.	Well Type:	OIL		
Well Name and No.:	GMX Kriss Unit 1-8	Well Location:	8,8,35	County:	Thomas
				State:	Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
AA2	125	1/4 Polyflake, 1/4# Defoamer, 10% Salt, .8% C-15, 5# Gilsonte, 3% Mag Chem 10CR	70897, 19578 Santiago	Front	Back
A-CON	400	3% CC, 1/4# Polyflake	14355, 37724 Willie	Front	Back
60/40 POZ	30		70897, 19578	Front	Back

Lead/Tail:	Weight #1 Gal.	Cu/Ft/sk	Water Requirements	CU. FT.	Man Hours / Personnel	
Lead:	15	1.41	5.78	176.25	TT Man Hours:	72
Tail:	11.6	2.77	16.75	1108	# of Men on Job:	4

Time (am/pm)	(BPM)	Volume (BBLS)	Pumps		Pressure(PSI)		Description of Operation and Materials	
			T	C	Tubing	Casing		
20:00							ON LOCATION & SAFETY MEETING	
20:30							RIG UP	
11:00 PM							RIG TO CIRCULATE	
11:30 PM							CIRCULATE	
12:35 AM		8.8 slurry					PUMP RAT HOLE 30SX 60/40	
0:52							PRESSURE TEST TO 3200PSI	
							RIG TO P.T.	
12:53 AM	3	11.9				80	PUMP 500GALLONS SUPER FLUSH	
0:59	3.1	5				80	PUMP 5BBL SPACER	
1:04	3.3	31.3 slurry				120	PUMP TAIL 125SX @ 15#	
1:14							SHUTDOWN / DROP PLUG / W.P.	
1:30	4.5	10				60	DISPLACE W/ 47BBL WATER	
	4.5	20				60		
	7	30				160		
	7	40				170		
	7	47				170	SWITCH TO MUDD	
	5.8	60				130		
	6.1	70				160		
	6.7	80				150		
	6.6	90				190		
	6.5	100				130		
	6.4	106				400	SLOW RATE TO 2.1 @ 200BPM	
2:00	2	116.1				430	LAND PLUG PRESSURE UP TO 1500PSI	
Size Hole	7 7/8"	Depth				TYPE	Plug Container	
Size & Wt. Csg.	5 1/2" 15.5#	Depth	4900'	New / Used		Packer	Depth	
D.V. TOOL	2900'	Depth				Retainer	Depth	
Top Plugs		Type				Perfs	CIBP	

Customer Signature: <i>X</i>	Basic Representative:	Daniel Beck
	Basic Signature:	<i>Daniel Beck</i>
	Date of Service:	3/28/2017



Liberal Yard #1717 - Phone 620-624-2277 - 1700 S. Country Estates Road, Liberal KS 67901

PRESSURE PUMPING

Job Log

Customer:	Val Energy Inc.	Cement Pump No.:	37223, 19919 9Hrs.	Operator TRK No.:	78938	
Address:		Ticket #:	1718 14316 L	Bulk TRK No.:	70897, 19578 Santiago	14355, 37724 Willie
City, State, Zip:		Job Type:	Z42 - Cement Production Casing			
Service District:	1718-Liberal Ks	Well Type:	OIL			
Well Name and No.:	GMX Kriss Unit 1-8	Well Location:	8,8,35	County:	Thomas	State: Ks

Type of Cmt	Sacks	Additives	Truck Loaded On		
			70897, 19578 Santiago	Front	Back
			14355, 37724 Willie	Front	Back
				Front	Back

Lead/Tail:	Weight #1 Gal.	Yield	Water Requirements	CU. FT.	Man Hours / Personnel
Lead:					Man Hours:
Tail:					# of Men on Job:

Time (am/pm)	(BPM)	Volume (BBS)	Pumps		Pressure(PSI)		Description of Operation and Materials
			T	C	Tubing	Casing	
2:03							RELEASE BACK -- FLOAT HELD
2:10							DROP OPENING TOOL
2:25 AM		1			1500		PUMP OPENING TOOL OPEN @ 1500PSI
2:27 AM							SHUTDOWN / SWITCH TO RIG TO CIRCULATE
3:00 AM							RIG TO P.T.
3:10	6.9	197.3 slurry			260		PUMP TAIL 400SX @ 11.6#
3:37							SHUTDOWN / DROP PLUG / W.P.
3:53 AM	2.5	10			130		DISPLACE
	7	20			400		
	6.9	30			470		
	6.9	40			540		
	6.9	50			580		
	6.9	59			580		SLOW RATE TO 2.3BPM @ 500PSI
4:10	2.3	69			550		LAND PLUG PRESSURE UP TO 1550PSI
4:13							RELEASE BACK -- FLOAT HELD
							JOB COMPLETE

Size Hole	7 7/8"	Depth			TYPE	
Size & Wt. Csg.	5 1/2" 15.5#	Depth	4900'	New / Used	Packer	Depth
tbg.		Depth			Retainer	Depth
Top Plugs	2900'	Type			Perfs	CIBP

Customer Signature: <i>[Signature]</i>	Basic Representative:	Daniel Beck
	Basic Signature:	<i>Daniel Beck</i>
	Date of Service:	3/28/2017

Val Energy Inc.
GMXKRISUNIT#1-8

