



PO Box 884, Chanute, KS 66720
620-431-9210 or 800-467-8676

8050
7944

TICKET NUMBER 51776
LOCATION Oakley Ks
FOREMAN Jerry Y

FIELD TICKET & TREATMENT REPORT
CEMENT

Invoice # 810139 Ks

| DATE | CUSTOMER # | WELL NAME & NUMBER | SECTION | TOWNSHIP | RANGE | COUNTY | |
|-------------|------------|------------------------|-----------------|-----------|--------|---------|--------|
| 4-23-17 | 2777 | Voth 1-4 | 4 | 12S | 32W | Logan | |
| CUSTOMER | | Mailing Address | | TRUCK # | DRIVER | TRUCK # | DRIVER |
| Culbreath | | 3501 South Yale Avenue | | 731 | Cory D | | |
| CITY: Tulsa | | STATE: OK | ZIP CODE: 74135 | 479 | Walt D | | |
| | | | | 529-7-127 | | | |

JOB TYPE 2 Stage HOLE SIZE 7 7/8 HOLE DEPTH 4771 CASING SIZE & WEIGHT 5 1/2 15.5#
 CASING DEPTH 4769 DRILL PIPE _____ TUBING _____ OTHER DV @ 2576
 SLURRY WEIGHT 14.2/11.6 SLURRY VOL 1.42/1.89 WATER gal/sk _____ CEMENT LEFT in CASING 42'
 DISPLACEMENT 112#/614 DISPLACEMENT PSI _____ MIX PSI _____ RATE _____

REMARKS: Safety meeting & rig up on Southwind & run float eq. scratches on 3, 4, 5, 10, 11, 12, 13, 14, 15, 16, 115 centralizers on 3, 5, 7, 9, 11, 13, 15, 115, 20, 30 baskets on 4, 21, 51 AFU Tool on top of 51 spot @ 2576 casing to bottom pump ball thr & circulate Vis 36 pump 5 bbl H₂O, mud flush, 20 bbl KCL mix 175 sks thixobland III shut down release plug wash pumps lines displac with 114 3/4 bbl final lift 800# plug landed @ 1400# released back a float held open tool 900# & circulate 3 hrs pump 5 H₂O mud flush 5 H₂O after mix 400 sks lite blend III shut down clean pumps lines & release plug displac with 63 bbl fresh water final lift 500# plug landed steel closed @ 1250# released back a float held 20 sks mbase hole 30 sks rat
 Thank you Jerry & crew

| ACCOUNT CODE | QUANTITY or UNITS | DESCRIPTION of SERVICES or PRODUCT | UNIT PRICE | TOTAL |
|--------------|-------------------|------------------------------------|------------|----------|
| CE0453 | 1 | PUMP CHARGE | 2800.00 | 2800.00 |
| CE0002 | 5 | MILEAGE | 7.15 | 35.75 |
| CE0711 | | ten mileage delivery | 66.00 | 66.00 |
| CC5862 | 175 sks | thixobland III | 26.00 | 4550.00 |
| CC6077 | 875# | Kal seal | 50 | 437.50 |
| CC5831 | 450 sks | lite blend III | 17.50 | 7875.00 |
| CC6075 | 113 # | flb seal | 3.00 | 339.00 |
| CC5301 | 2 gal | KCL | 39.00 | 78.00 |
| CC6125 | 1000 gal | mud flush | 65 | 650.00 |
| CP8676 | 40 | 5 1/2 scratches | 75.00 | 3000.00 |
| CP8485 | 1 | 5 1/2 AFU float shoe | 585.00 | 585.00 |
| CP8254 | 1 | 5 1/2 latch down assy | 400.00 | 400.00 |
| CP8554 | 10 | 5 1/2 centralizers | 81.00 | 810.00 |
| CP8629 | 3 | 5 1/2 baskets | 385.00 | 1155.00 |
| CP8801 | 1 | 5 1/2 DV Tool | 5970.00 | 5970.00 |
| | | subtotal | | 29345.25 |
| | | | -35.8 | 10270.84 |
| | | subtotal | | 19074.41 |
| | | SALES TAX | | 1344.17 |
| | | ESTIMATED TOTAL | | 20418.58 |

AUTHORIZATION [Signature] TITLE _____ DATE _____

I acknowledge that the payment terms, unless specifically amended in writing on the front of the form or in the customer's account records, at our office, and conditions of service on the back of this form are in effect for services identified on this form.