

810 E 7TH
 PO Box 92
 EUREKA, KS 67045
 (620) 583-5561



Cement or Acid Field Report

Ticket No. **4449**
 Foreman David Gardner
 Camp Eureka

Date	Cust. ID #	Lease & Well Number	Section	Township	Range	County	State
4-25-19	1097	L D Donley #20-1				Cowley	KS
Customer			Safety Meeting	Unit #	Driver	Unit #	Driver
Alton Oil LLC			DG	105	Jason		
Mailing Address			JH	114	Caleb		
P.O. Box 117			CG				
City	State	Zip Code					
Winfield	KS	67156					

Job Type P.T.A. Oldwell Hole Depth _____ Slurry Vol. 34 Bbl Tubing _____
 Casing Depth _____ Hole Size _____ Slurry Wt. 14[#] Drill Pipe _____
 Casing Size & Wt. 5 1/2" Cement Left in Casing _____ Water Gall/SK 6.5 Other _____
 Displacement _____ Displacement PSI _____ Bump Plug to _____ BPM _____

Remarks: Safety Meeting. Shot 5 1/2" casing off @ 1519'. Rig pulled casing up to 269'. Rig up to 5 1/2" casing. Mixed 120 sks 60/40 Pozmix Cement w/ 4% Gel @ 14#/gal, yield 1.36 = 29 Bbl slurry shut down. Good cement returns to surface. Rig pulled remaining 5 1/2" casing. Top well off w/ 20 sks cement. Well stayed full. Job complete. Rig down.

Total Cement = 140 sks = 34 Bbl Slurry.

Code	Qty or Units	Description of Product or Services	Unit Price	Total
C105	1	Pump Charge	785.00	785.00
C107	50	Mileage	4.20	210.00
C203	140 sks	60/40 Pozmix Cement	13.40	1876.00
C206	480 [#]	Gel @ 4%	.21	100.80
C108B	6.02 Tons	Ton Mileage - Bulk Truck	1.40	421.40
<i>Thank You</i>				
			Sub Total	3,393.20
			Less 5%	180.69
			6.5 % Sales Tax	220.56
Authorization _____ Title _____			Total	3,433.07

I agree to the payment terms and conditions of services provided on the back of this job ticket. Any amendments to payment terms must be in writing on the front of this job ticket or in the Customer's records at ELITE's office.

Quality Wireline Services, LLC

Service Order No.
0524

30060 N. Hwy 281 • P.O. Box 468 • Pratt, Kansas 67124 • 620-388-2309 or 620-727-6964 • Fax 620-672-3663

Date 4-25-19

Company <i>Quality Wireline Services, LLC</i>			Client Order # <i>0W</i>		
Billing Address <i>PO Box 117</i>		City <i>WILMINGTON</i>	State <i>KS</i>	Zip <i>67156</i>	
Lease & Well # <i>LD D... = 20-1</i>		Field Name		Legal Description (coordinates)	
County <i>COMBEE</i>	State	Casing Size	Casing Weight		
Fluid Level (surface)	Reading From	Customer T.D.	Quality Wire Line T.D.		
Engineer <i>D Zell</i>	Operator	Operator	Unit# <i>01</i>		

Product Code	Description	Qty	Unit Price	Depth		\$ Amount
				From	To	
	<i>5 1/2 CIBP</i>					<i>9,000⁰⁰</i>
	<i>Setting charge @ 2915</i>					<i>1,500⁰⁰</i>
	<i>25K cement Dump Bore @ 2915</i>				<i>2915</i>	<i>8,100⁰⁰</i>
	<i>5 1/2 casing cut @ 1515</i>				<i>1515</i>	<i>2,100⁰⁰</i>
	<i>Service charge</i>					<i>1,500⁰⁰</i>

SUBTOTAL	<i>7,000⁰⁰</i>
DISCOUNT	
SUBTOTAL	<i>2,750⁰⁰</i>
TAX	
NET TOTAL	

Customer

Taylor Printing, Inc. • 620-672-3656

Donkey 2750.00
Shoot off pipe

