



RJ Energy

22082 NE Neosho Rd Garnett. Kansas 66032

Brewer 4-A

			Start 1-23-19
			Finish 1-31-19
7	soil	7	
25	clay/gravel	32	
64	shale	96	
77	lime	173	
99	shale	272	
113	lime	385	
49	shale	434	
70	lime	504	Set 40' of 7" w/5sxs
5	shale	509	Ran 970' of 2 7/8
47	lime	556	cemented to surface 125sxs
183	shale	739	
28	lime	767	
49	shale	816	
26	lime	842	
21	shale	863	
12	lime	875	
13	shale	888	
3	lime	891	
12	shale	903	
4	lime	907	
34	shale	941	
4	Sandy shale	945	odor
5	bkn sand	950	good show
26	Shale	976	T.D.